

GLOBAL TENDER NOTICE)
(Tender No: IPGL/YARD CRANES/2018)

Sealed tenders in two-bid system (Technical & Price Bids) are invited on behalf of **India Ports Global Ltd (IPGL)**, from reputed manufacturers fulfilling the Minimum Eligibility Criteria (MEC). The scope of works, details of time schedule and EMD to be submitted by Tenderers for participation in this tender are given below:

i)	Scope of work	Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton. Capacity Yard Cranes at Shahid Beheshti Port, Chabahar, Islamic Republic of Iran.
ii)	Earnest Money Deposit(EMD)	Euros 70800/- (Euro Seventy Thousand Eight Hundred only) , Indian Rupees 55,30,000/- (INR Fifty Five Lakhs Thirty Thousands Only) in favour of IPGL in the form of Bank Guarantee, as per Annex-II of Tender Document (Vol-I), from any Nationalised or Scheduled Bank having its branch at Mumbai OR Demand Draft of above said amount in favour of IPGL payable at Mumbai., for all six cranes. For Three Nos All Terrain cranes (100 T) EMD shall be: Euro 3,77,00 /- (Euro Thirty Seven Thousand Seven Hundred only)/- Or Indian Rupees 29,62,000 /- (INR Twenty Nine Lakhs Sixty Two Thousand only) For Three Nos Rough Terrain cranes (60 T): Euro 3,30,00 /- (Euro Thirty Three Thousand only)/- Or Indian Rupees 25,97,000/- (INR Twenty Five Lakhs Ninety Seven Thousand only)
iii)	Sale of Tender Document	On all working days (1000 hrs to 1700 hrs) from 26-02-2018 during office hours at the office of the Managing Director, India Ports Global . Ltd., 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai-400010. Tender document will not be sent by post/courier.
iv)	Pre-Bid Meeting	On 12-03-2018, at 1030 Hrs at Conference Hall of India Ports Global Ltd, 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai-400010
v)	Cost of Tender Document (set of two copies)	Rs. 10,000/- (Rupees Ten Thousand only) or Euro.130.00 (Euro One Hundred Thirty only) in the form of Demand Draft (non-refundable) drawn on any scheduled bank having its branch at Mumbai in favour of India Ports Global Ltd. Tender Document shall have to be collected by the party through an authorised person/ Agent. The Tender document detailing the terms & conditions and the technical requirements can also be downloaded from the web sites: http://ipa.nic.in , http://www.jnport.gov.in and http://www.kandlaport.gov.in from 26-02-2018 onwards till the date of submission of tender. The downloading of tender document shall be carried out strictly as provided on web site. In such case, the Cost of tender document can be deposited at the time of submission of the tender. Tender document will not be sent by post/courier.
vi)	Due date for submission of Tender Document	On or before 10th April, 2018 up to 1500 hrs at the office of the India Ports Global Ltd, 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai-400010 .
vii)	Date Of opening of Technical Bid	On 10th April, 2018 at 1530 hrs. at Conference Hall, India Ports Global Ltd, 4 th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai-400010.

Managing Director,

For India Ports Global Ltd,

4th Floor, Nirman Bhavan,

M.P. Road, Mazgaon,

Mumbai-400010, India

Email:-md.indiaportsglobal@gmail.com

CONTENTS

Sr No	DESCRIPTIONS	Page No
	VOLUME – I	
1	GLOBAL TENDER NOTICE	1 - 2
2	CONTENTS--PAGE NUMBERWISE INDEX	3
3	INSTRUCTIONS TO TENDERERS (ITT)	4 - 18
4	GENERAL CONDITIONS OF CONTRACT (GCC)	19 - 44
5	SECTION 4 - ENVIRONMENTAL CODITIONS AT CHABAHAR	45 - 48
6	ANNEXTURES-I TO VII	49 - 62
7	SCHEDUALS 1-10A	63 - 76
8	PRICE- SCHEDUAL 11- PART I A-IB	
9	PRICE- SCHEDUAL 11- PART I A & I B	77 - 78
10	PRICE- SCHEDUAL 11- PART II	79
11	SCHEDUAL 12 INTENGRITY AGREEMENT	80 - 82
12	SCHEDULE 13 CHECK LIST	83 - 84
13	SCHEDUAL 14 CONFIDENTIALITY AND NON-DISCLOSURE AGREEMENT	85 - 87
14	SCHEDUAL 15 DETAILS OF KEY PERSONNEL	88
15	SCHEDUAL 16 CURRENT COMMITMENTS IN HAND	89
16	SCHEDUAL 17 DETAILS OF WORKS COMPLETED IN PAST	90
17	SCHEDUAL 18 EXPERIENCE IN SIMILAR WORKS	91 - 93
	VOLUME – II	94
1	TECHNICAL SPECIFICATION	95 - 106

2. INSTRUCTIONS TO TENDERERS (ITT)

2.1 Sealed tenders in two-bid system (Technical & Price Bid), are invited on behalf of India Ports Global Ltd (IPGL), for the following work : –

Name of the work: Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton. Capacity Yard Cranes at Shahid Beheshti Port, Chabahar.

2.1.1 Minimum Eligibility Criteria (MEC)

a. Financial Standing: For all six Yard Cranes

The average annual financial turnover of the tenderer over the past three years shall be at least EURO 7,265,000/- (Euro Seven Million Two Hundred Sixty Five Thousand only) or Indian Rupees 56,75,00000/- (Rupees Fifty Six Crores Seventy Five Lakhs only)

Note: In case the Tenderer desires to quote for only one category, then the following criteria would apply:

- (i) For three nos all terrain cranes (100 T): Euro 3,77,0000/- (Euro Three Million Seven Hundred Seventy Seven Thousand only)/-Indian Rupees 29,62,00000 /- (INR Twenty Nine Crores Sixty Two Lakhs only)
- (ii) For three nos Rough terrain cranes (60 T): Euro 3,30,6000/- (Euro Three Million Three Hundred Six Thousand only)/- Indian Rupees 25,97,00000 /- (INR Twenty Five Crores Ninety Seven Lakhs only)

b. Experience:

The tenderer should be in the business of designing, manufacturing, Supplying and Commissioning of YARD CRANES (of the type quoted), at least for the last seven (07) years. Copy of work order and/or completion certificate for the year 2011 or before to be submitted.

c. Capacity and Capability:

1. For 100 Ton Capacity All-Terrain (AT) Yard Cranes:

The tenderer should have supplied at least three (3) nos. of Yard Cranes All-Terrain (AT) with minimum 100 ton Lifting Capacity under hook during the last seven (07) years.

Copy of work order/s and completion certificate/s for the period mentioned to be submitted.

2. For 60 Ton Capacity Rough-Terrain (RT) Yard Cranes:

The tenderer should have supplied at least three (3) nos. of Yard Cranes Rough-Terrain (RT) with minimum 60 ton Lifting Capacity under hook during the last seven (07) years.

Copy of work order/s and completion certificate/s for the period mentioned to be submitted.

d. Satisfactory Performance:

At least Three (03) Yard Cranes (any type) supplied in the last seven (07) years must have completed warranty period satisfactorily. Copies of certificate from client for satisfactory completion of warranty period to be submitted.

Note: During last seven years means during last seven years ending last day of the month previous to the one in which the tender is published / uploaded on website

e. Recent Business Activities:

The tenderer should have supplied or is in the process of manufacturing at least Three (03) Yard Cranes during the last two (02) years.

All the tenderers participating in this tender shall be evaluated so as to meet the above requirements of Yard Cranes **separately** for 100 ton (AT) and 60 Ton (RT) capacity. The price schedule for both categories of Yard cranes should be submitted in separate sealed envelope duly super scribed on it and both the sealed envelopes shall be kept and submitted in sealed **envelope 4**. They will be separately evaluated and the selected bidder for the same shall be separately announced. To clarify further, the parties for the award of both capacity Yard Cranes may be separate.

Note: If the Tenderer is a subsidiary Company, then for the purpose of meeting MEC criteria of clause 2.1.1, documents submitted by the tenderer of its holding Company and/or its sister company can be considered, provided the holding company certifies that the tenderer and/or its sister company is their subsidiary and the holding company is severally and jointly responsible for compliance of the contract terms and conditions.

2.2 LAST DATE FOR SUBMISSION OF TENDER

2.2.1 Tenders shall be received in the office of the Managing Director, India Ports Global Ltd, 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai-400010, up to 1500 hrs on **10th April, 2018**.

2.2.2 IPGL, may at its own discretion, reserves the right to extend the date for receipt of tender. Tenders received after the aforesaid time and date or the extended time and date, if any, shall be returned unopened to the Tenderer. Tenderers to note that IPGL shall not be responsible for late receipt of any offer due to postal delays or any other delay for whatsoever reasons.

2.3 TENDERER TO INFORM HIMSELF FULLY

- 2.3.1** The Tenderer is expected to examine carefully the contents of the tender document like, Instructions to the Tenderers, General Conditions, and scope of work, annexure and schedules, check-list of documents to be submitted along with the tender etc. Failure to comply with the requirements of the tender will be at the Tenderer's own risk. It would be deemed that prior to the submission of the tender the Tenderer has made a complete and careful examination of requirements and other information set out in the tender document. The Tenderer shall be deemed to have, visited the site and surroundings and have obtained all necessary information in all the matters whatsoever that might influence while carrying out the works as per the conditions of the tender and to satisfy himself to sufficiency of his tender, etc.
- 2.3.2** The Tenderer is advised to get acquainted himself with the job involved at the site, like availability of labour, means of transport, communication facilities, local laws and bye laws in force. The tenderer is essentially required to be abreast of latest Rules and Regulations in force as regards to local port authority and any other statutory bodies as well as security regulation for the permission to collect all information that may be necessary for preparing and submitting the tender and entering into Contract with IPGL.
- 2.3.3** Tenderer shall bear all costs associated with the preparation and submission of his tender and IPGL will in no case be responsible or liable for these costs, regardless of the conduct or outcome of the tendering process.
- 2.3.4** The Tenderer and/or his representatives will be granted permits to visit the site for the purpose of inspection, on receipt of a formal written request. The Tenderer will be fully responsible for any injury (whether fatal or otherwise) to himself or his representatives for any loss or damage to property or for any other loss, damage, costs and expenses whatsoever caused which but for the granting of such permission would not have arisen. The Tenderer will be liable to indemnify the Employer against any loss or damage to the property of the Employer or neighbouring property which may be caused due to any act of the Tenderer or his representatives.
- 2.4** **EARNEST MONEY DEPOSIT (EMD)**
- 2.4.1** The tender shall be accompanied by Earnest Money Deposit as stipulated in the tender notice. **The tender not accompanied with EMD shall be treated invalid.** The E.M.D. shall be submitted in the form of Bank Guarantee (BG) as per enclosed format at **Annex-II (Vol. I of the Tender Document)** drawn in favour of India Ports Global Ltd, Mumbai, from any Nationalised/Scheduled Bank (Nationalised/Scheduled Bank shall mean a bank defined under section 2 (e) of the Reserve Bank of India Act 1974) having its branch at Mumbai. However, alternatively, Demand Draft (DD), in favour of IPGL, Mumbai, drawn on any Nationalised / scheduled bank enlisted under RBI, in favour of India Ports Global Ltd, payable at Mumbai, for specified amount in the tender for EMD, can be acceptable.

2.4.2 In the event of tenderer withdrawing his tender before the expiry of tender validity period of **180 days** from the date of opening of technical bid, the tender submitted by the tenderer shall be cancelled and EMD shall be forfeited.

2.4.3 The Earnest Money Deposit of unsuccessful Tenderers shall be returned on award of Contract to the successful Tenderer. No interest shall be payable on the amount of E.M.D in any case. The Earnest Money Deposit of the successful Tenderer shall be refunded only on receipt of Performance Guarantee as stipulated in the tender.

2.4.4 IPGL reserves the right to forfeit the Earnest Money Deposit in respect of successful Tenderer, if he fails to furnish the necessary Bank Guarantee towards performance within **45** days and enter into a Contract within 30 days from the date of issue of Letter of Acceptance (LOA) as per tender.

2.4.5 EMD shall not be enclosed with the sealed covers containing technical offers, but shall be submitted separately in a properly sealed envelope so super scribed.

2.5 IPGL'S Right to Annul the Bidding Process

2.5 Notwithstanding anything contained in this tender document, IPGL reserves the right to annul the bidding process at any time without any liability or any obligation for such annulment, without assigning any reason.

It is clarified that in case the tender process is annulled by IPGL under the provision of Clause 2.5.1, the

EMD of the Bidders shall be returned within 21 days from the date of notice of annulment.

2.5 IPGL reserves the right to invite revised Technical Tenders and / or revised Financial Tenders from Bidders with or without amendment of the tender document at any stage, without liability or any obligation for such invitation and without assigning any reason.

2.5.3 IPGL reserves the right to reject any Tender if at any time, a material misrepresentation is made or uncovered OR the Bidder does not respond promptly and thoroughly to requests for supplemental information required for the evaluation of the tender.

2.6 TENDER VALIDITY:

The tender shall remain valid for acceptance for a period of **180 days** from the date fixed for opening of Technical Bid. IPGL reserves their right to extend the period of validity for a specific time. The request and the response, there to, shall be made in writing by post or by E-mail. However, in the event of the tenderer agreeing to the request, he shall not be permitted to modify his tender. In the event of the tenderer agreeing to the extension, the Tenderer shall correspondingly extend the validity of the tender suitably along with valid extension of the Bank Guarantee furnished towards EMD against this Tender. In case tenderers do not agree to extend the validity of their offer beyond the validity period, EMD of such tenderers shall be refunded after award of the contract.

2.7 AUTHORITY FOR SIGNING TENDER DOCUMENTS

2.7.1 The tender, if submitted on behalf of principals or a Partnership Firm should be signed either by all the partners or some of the partners or other person/s holding a valid “Power of Attorney” from other partners or all the partners constituting the firm or the Principals as the case may be.

2.7.2 In the event, the tender is signed by some of the partners or other persons or the Authorised Distributor / Dealer / Licensee, the Tender should be accompanied by a valid Power of Attorney duly executed by partners/Principals specifying that the partners or person/s or Authorised Distributor / Dealer / Licensee, signing the tender has the authority to bind them or the firm as the case may be, in all matters pertaining to the tender.

2.7.3 In case of a Company, the tender should be signed by a person holding a valid Power of Attorney executed in his favour in accordance with the constitution of the Company.

2.7.4 In case of submission of tender in Joint Venture (JV), the following conditions shall be complied by the tenderer:

- JV being registered in India for at least 7 years for supply of equipment.
- The JV in India demonstrating their active involvement in the business activity over the last two financial or calendar years preceding the tender.
- The JV agreement being documented and subject to scrutiny/assessment by IPGL.
- The term of JV being at least equal to the warranty period completion of the equipment/work being tendered.
- The JV Agreement providing for technical support including but not limited to the supply of spares during the economical lifetime of the equipment being tendered.
- The experience of each JV partner would be considered on par with other Original Equipment Manufacturer subject to the collective experience of partners meeting the standards established in capacity and capability criteria indicated in MEC.
- The guarantee/warranty for the equipment up to the expiry of the structural guarantee should be jointly and severally undertaken by the JV partner.

2.7.5 In case of tender submitted by the **partnership firm** then the partnership firm shall comply the JV clauses above for qualifying in the subject tender.

2.8 ELIGIBILITY IN CASE OF TENDER SUBMITTED BY OEM /AUTHORISED DISTRIBUTOR

/ DEALER / LINCENSEE:

In case, the Tenderer is an Original Equipment Manufacturer (OEM) who in turn intends to execute the order through their Authorised Distributor / Dealer / Licensee or Business Partner, such nominated firm must fulfil all the minimum qualifying criteria as stipulated in Clause No. 2.1.1 of this tender document to get qualified for further evaluation. The OEM and his authorised dealer/distributor / Licensee cannot participate simultaneously in this tender. **In case, OEM and his authorised**

distributor / dealer /Licensee participate in this tender simultaneously, then only the offer of OEM will be considered.

2.9 AMENDMENTS

2.9.1 At any time, prior to the last date for submission of tenders, IPGL reserves the right to amend and modify the tender document. The amendments so carried out shall be forwarded to all the prospective Tenderers prior to the last date for submission of the tender in writing either by post or by Fax and email including displaying the said amendment on JNPT/KPT/IPA web sites. The prospective Tenderers shall immediately acknowledge receipt thereof either by post or by fax.

2.9.2 The amendment so carried out shall form part of the tender and shall be binding upon the Tenderers. IPGL may at their discretion, extend the last date for submission of the tender, to enable the Tenderers to have reasonable time to submit their tender after taking into consideration such amendments.

2.10 ERRORS IN THE TENDER DOCUMENT

2.10.1 Tender shall be prepared, signed and submitted only by that bidder in whose name the tender documents have been issued. The tender shall be typed or written in indelible ink and all pages of the tender shall be signed.

2.10.2 The Tenderer shall submit complete tender and the same shall be without alterations, interlineations or erasure except those to accord that instructions issued by the IPGL or as may be necessary to correct errors made by the Tenderers. Person or persons signing the tender shall initial all such cancellations, alterations or amendments. If any discrepancies found in figures and words while reading the rates in the Price Schedule the rate quoted in words shall supersede the figures. In the event of any difference between the unit rate and the total amount stated therein, the unit rate should be reckoned as the correct one.

2.11 MODIFICATION, SUBSTITUTION AND WITHDRAWAL OF PROPOSAL

The Tenderer may modify, substitute or withdraw his proposal after submission, provided that written notice of modification, substitution or withdrawal is received by the Employer before the closing time on due date of submission. No offer shall be modified, substituted or withdrawn by the Tenderer after the closing time on due date. The Tenderer's modification, substitution or withdrawal notice shall be addressed to the Managing Director, India Ports Global Ltd, 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai- 400010, with outer envelope clearly marked as Modification, substitution or withdrawal of the tender. Withdrawal of a proposal during the interval between closing time on proposed due date and expiry of the proposal validity period would result in forfeiture of EMD in accordance with clause 2.4.2 (Volume-I of Tender Document).

2.11.1 STAMP DUTY & OTHER EXPENSES:

All costs, charges and expenses including any duty in connection with the Contract as well as preparations and completions of agreement including registration of same by the tenderer, **if he wishes to do so**, shall be payable by the Tenderer. The Tenderer shall ascertain the taxes and duties to be paid on his own due diligence before the submission of the bid. All taxes duties, to be paid to any statutory bodies in places other than destination country shall be paid by the tenderer.

The Bidder shall quote their CIF prices (Incoterm 2010) with insurance till receipt of equipment at the port of destination, inclusive of all taxes and duties related to their country of export. The Bidder shall exclude from his price, the custom duty / related taxes (if any payable in destination country) for those items / equipments only which are appearing in the Price Schedule. These taxes / duties related to destination country, if payable, shall be borne by IPGL.

For avoidance of doubt,

- (i) It is further clarified that CIF value includes all dues at port of origin and vessel related charges at the disport, including insurance till receipt of equipment at the port of destination.
- (ii) Wharfage at disport (if applicable) will be reimbursed to the bidder against the documentary evidence.
- (iii) Taxes and duties for those items / equipments which are appearing in the Price schedule, the custom duty in destination country shall be borne by IPGL.

2.12 CONTRACT WORK AND CONTRACT PRICE:

2.12.1 The work to be carried out (hereinafter referred to as "the Contract Work") and the Price for the same (hereinafter called "the Contract Price") shall include the work described in the specifications, schedules, drawings, etc. annexed hereto.

2.12.2 Except where otherwise expressly provided, the Contractor shall provide all materials, labour and Specified and although there may be errors and omissions in the specifications.

2.12.3 The Scope of Works, under this contract is as mentioned below.

“ Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. Rough-Terrain 60 Ton. Capacity yard Cranes at Shahid Behesti Port, Chabahar.”

2.12.4 Contract Price: Price shall be inclusive of all charges for Design, Manufacture, Transportation, including Transit/Marine and other Insurance, Handling, Supply and Delivery, Receipt of all Equipment/Items and handed over at Site, Installation, Trials, Testing, Commissioning of Equipment and Insurance at Site, Training of IPGL personnel at IPGL site, Cost of O & M Manuals and Training Manuals as per Contractual Conditions, cost of the recommended maintenance tools supplied along with each equipment as per list of tools i.e. Schedule 10 (Volume-I), warranty support as per

Contractual conditions and all incidental expenses towards installation/commissioning of the equipment will be borne by contractor.

- 2.12.5** Contractors shall arrange for training of the staff of Employer for training on Crane Control System and Crane Monitoring System at IPGL site. This training shall be conducted by the manufacturer's qualified and experienced personnel while carrying out the test and trial runs of equipments.

Tenderer are required to quote in Price Schedule 11, part II for all the spare parts & Tools as per Clause 32 A, B & C Spares for 60 ton Capacity and Clause 18,19 & 20 for 100 ton Capacity Yard Cranes in Volume II of the tender, which is optional on part of IPGL and not considered for evaluation of the bids,. However, IPGL reserves the right to review the same at the time of award of contract to the successful tenderer.

Spare Parts/Tools as listed in respective schedule of tender are optional and not to be considered for evaluation of the bid. However, the bidder has to confirm that prices quoted for spares and tools will remain valid for 2 years from date of Final Acceptance.

2.12.6 LANGUAGE OF TENDER

The Tender submitted by the Tenderer and all correspondence and documents relating to the Tender exchanged by the Tenderer and the IPGL shall be written in the English language. Any printed literature, other than English language, shall be accompanied by an English translation, in which case, for purpose of interpretation of the tender, the English translation shall govern. Anything given in a language other than English shall not be taken into consideration for any purpose.

For Financial Standing, Audited Reports in Language other than English, the translation in English duly certified by a Chartered Accountant shall be considered for evaluation.

2.13 CONVERSION OF SINGLE CURRENCY

The bidders shall be allowed to quote the tender offer in either US Dollars or Euros or Indian Rupees. To facilitate evaluation and comparison, IPGL shall convert all tender Prices, expressed in Euros into Indian Rupees, at the bill selling rate quoted by State Bank of India on the date of opening of tender i.e. date of opening of Technical Bid. If on this date, due to any reasons such exchange rates are not available (Forex Market may be closed) the latest available rates prior to the date of opening shall be considered. The due payment of the contract shall be paid in same currency quoted.

2.14 TENDER SUBMISSION

The tender submitted by Tenderer shall comprise the following:

- 2.14.1** A covering letter along with check list – **Schedule 13** (Volume I) giving details of the documents being submitted with tender confirming validity of bid for 180 days & submission of Earnest Money

Deposit and the Tender Document fee, if not already paid - **Envelope 1** so super scribed with the contents therein.

2.14.2 Earnest Money Deposit as per tender condition- **Envelope 2** so super scribed with the contents therein.

2.14.3 The tender document (**downloaded from JNPT, KPT, IPA web-site**) to be submitted in two sets, one being marked as "**ORIGINAL**" and other as "**DUPLICATE**". (Technical Bid), with each page of it duly signed by the authorised person and stamped with company's seal in token of having been read and accepted the tender conditions along with Letter of application cum Tender form duly signed by the person / persons who is/are competent to sign as per format enclosed to this tender document and **TECHNICAL BID**. A scanned copy of the signed documents along with **MS-WORD/EXCEL** copy (as the case may be) of the technical bid shall also be submitted on a CD/pen drive. - **Envelope 3** so super scribed with the contents therein.

2.14.4 **Price Bid- Envelope 4** so super scribed with the contents therein. Price schedule Part 1A, 1B and part II shall be submitted in separate sealed envelopes and shall be kept in **Envelope 4**

2.14.5 One Duplicate Copy of Technical Bid (clearly marked) of the offer shall be submitted along with the original offer as stated above in 2.14.3 in **Envelope 3** Tenderers are required to put each of the elements viz., Covering letter, Earnest Money Deposit, Technical Bid with tender form and Tender Document, Price Bid and Duplicate Copy of Technical Bid in separate sealed envelopes as stated above. These Four envelopes shall be super scribed as "Tender No. IPGL/YARD CRANES/2018 "Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. capacity and 3 Nos. of Rough-Terrain 60 Ton. capacity Yard Cranes at destination port and shall be addressed to The Managing Director, India Ports Global Ltd, 4th Floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai- 400010, Maharashtra State, India.

2.15 TECHNICAL BID

Technical Bid should not contain Prices i.e. it should not contain Schedule 11 i.e. Schedule of price. "Disclosure/indication of Price in the Technical Bid shall render the tender disqualified and rejected".

The Technical Bid shall comprise of the following information /documents which will be used in the evaluation of Tenders.

2.15.1 The Tenderer while submitting their offer for this Tender, shall also confirm in writing along with all relevant documents supporting to fact that they are meeting the MEC as specified at clause 2.1.1 of this tender document.

2.15.2 Particulars of the Tenderers as specified in the **Schedule 1 (Volume-I)** of this tender document.

2.15.3 Duly Audited Annual Financial Reports on financial standing of the Tenderer / holding Company including annual turnover, for the last three years, as per **Schedule 2 (Volume-I)** of this tender document.

2.15.4 Documentary evidence related to business registration/commencement.

- 2.15.5** Lists of orders executed during the last seven (7) years and documentary evidence that is copies of work orders indicating supply of Yard Cranes as per Clause 2.1.1.b.
- 2.15.6** Copies of certificates indicating supply of at least 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton. Capacity Yard Cranes supplied during last seven years as per Clause 2.1.1.c.
- 2.15.7** Copy of satisfactory performance certificate from the client after completion of warranty period of at least Three (3) numbers of Yard Cranes during the last Seven (7) years as per Clause 2.1.1.d.
- 2.15.8** Copy of the order (with price blanked), for supply of at least Three (3) numbers of Yard Cranes during last two (2) years as per Clause 2.1.1.e.
- 2.15.9** Technical data of the crane as per Clause 3 (Volume-II), Main Conditions of this tender document. Work Schedule showing as per **Schedule 3 (Volume-I)** of this tender document.
- 2.15.10** Details of the training programme to IPGL and/or its Associate employees as per Schedule 4 and Schedule 4 A (Volume-I) of this tender document. Training will be provided at Employer's site and shall focus on operation, maintenance and trouble shooting.
- 2.15.11** Quality Assurance Plan indicating all activities steps by step at various stage of project as per **Schedule 5 (Volume-I)** and details of instruments for Testing & quality control as per **Schedule 6 (Volume-I)** of this tender document.
- 2.15.12** Details of Sub Contractors (if applicable), involved in the various activities according to **Schedule 7 (Volume-I)** of this tender document.
- 2.15.13** Details of organisation showing hierarchy and key personnel i.e. Organisation chart.
- 2.15.14** Experience in having executed similar Works along with and other related details.
- 2.15.15** Tentative drawings of various arrangements of the crane as per clause 3.26 (Volume-I) of this tender document.
- 2.15.16** Arrangement for importing spare parts, tie up with local firms for supply of spare parts, if any and arrangement for after sales service. Tenderer shall submit the information as per **Schedule 8 (Volume- I)** of the Tender Document and list of spare-parts under **Schedule 10** for 100 Ton. (AT) Clause Nos. 18, 19 & 20 of Volume II and for 60 Ton. (RT) Clause Nos. 32 A, B & C of Volume II.
- 2.15.17** Details of major bought out items and its quality certification plan.
- 2.15.18** Operations and Maintenance Manuals as per **Schedule 10 A** of the Tender Documents Volume I.
- 2.15.19** Information regarding any current litigation.
- 2.15.20** Any other details, which shall establish the technical competency and any deviation from technical specification.
- 2.15.21** The deviations if any, shall be submitted as per **Schedule 9 (Volume-I)** of the Tender Document along with Technical Bid without disclosure of the Price adjustments for withdrawal of deviations

proposed by the Tenderer. However, the price adjustments proposed for withdrawal of Deviations if any, as specified by the tenderer in the **Schedule 9**, shall be submitted along with the PRICE SCHEDULE of the respective crane. If Price adjustments are not given in the price schedule, it is deemed that particular deviation does not bear any financial implication for withdrawal of deviation. In case there are no deviations, **Schedule 9** shall be stroked off by writing “**NO DEVIATIONS**” on it.

2.15.22 List of spare parts quoted as per **Schedule 10 (Volume-I)** without disclosure of the price. Refer Clause No. 2.14.19 above.

2.15.23 Undertaking to ensure Integrity: The tenderer shall give an undertaking that they have not made any payment or illegal gratification to any person /authority connected with the bid process so as to influence the bid process and have not committed any offence in connection with the bid. The bidder shall disclose any payments made or proposed to be made to any intermediaries (agent etc.) in connection with the bid.

2.15.24 Confidentiality and Non-Disclosure agreement: Except with the written consent of IPGL, the successful tenderer and its personnel shall not at any time communicate to any person or entity any confidential information acquired in the course of the Project execution or the services rendered, this contract or IPGL’s Business Operations nor shall the vendor/Consultant and its Personnel make public the recommendations formulated in the course of, or as a result of the services. However, in case of requirement of sharing of critical business/technical information with third party, a Non-disclosure agreement (**Schedule 14**) shall be signed between authorised official of the successful tenderer and IPGL.

Note: Technical offer with counter condition shall be liable for rejection and disqualification.

2.16 PRICE BID:

2.16.1 The “Price Bid” as per the **Price Schedule 11** of Vol.-I of the tender document shall contain following;

- i.** CIF Price of the equipment (means as per Incoterm 2010, with insurance till receipt of equipment at the port of destination, inclusive of all taxes and duties related to their country of export.
- ii.** CIF Price of spare parts/Tools.
- iii.** Price breakup of Spares and Tools as mentioned in **Schedule 11- part II (Vol-I)**.
- iv.** Cost towards inspection of equipment at contractor’s works (as per clause 3.24 Vol-I of the tender document) this shall deem to be included in the cost of the equipment.
- v.** Cost towards Training of IPGL personnel at IPGL site, Operation and Maintenance manuals.
- vi.** Cost towards Warranty support.

The expenses on the inspection at contractor’s works for the officers deputed shall include to and fro travelling expenses from IPGL to contractor’s works and vice-a-versa, lodging & boarding, local transportation at Contractor's works.

2.16.2 Conditional Price Bid shall be liable for rejection.

2.16.3 The “Price Bid” shall contain rates of Yard Cranes, as per the **Price Schedule of Volume-I of the tender document i.e. Schedule11**. The CIF Price Schedule shall contain all applicable taxes payable at country of origin , CIF Price of the equipment and spare parts / Tools as per **relevant Schedule of (Volume-I)** Price for Testing and Commissioning of the equipment, the cost for imparting training to IPGL personnel at work site i.e. Chabahar Port. It may be noted that Custom Duty at Chabahar is likely to be exempted for IPGL on import of ONLY those items / equipment appearing in the Price Schedule of this tender document. Anything other than the subjected to the contract is liable for duties as applicable. The bidder shall quote their CIF prices inclusive of all taxes and duties related to their country of export, it is further clarified that CIF value includes all dues at port of origin and vessel related charges at the disport, including insurance till receipt of equipment at disport. Wharfage at disport (if applicable) will be reimbursed to the bidder against the documentary evidence. Taxes and duties for those items / equipments which are appearing in the Price Schedule, the custom duty in destination port shall be borne by IPGL. The bidder shall exclude from his price the custom duty/related taxes if any, payable in destination port for the items / equipments appearing in the price schedule.

2.16.4 Tenderers shall quote the Total cost for the entire work as per Contract conditions and as per format given in the Price Schedule.

2.16.5 Tenderers shall quote for each and every item of the work of the Tender as per price schedule of the tender. Partial offer by any tenderer shall be liable for rejection and will not be considered by the IPGL.

2.17 PRE-BID CONFERENCE

IPGL shall hold a pre-bid meeting, in order to clarify and discuss issues with respect to the tender vis-à-vis terms and conditions or any other related issues. The meeting shall be held on **12-03-2018** at Conference Hall, 4th floor, Nirman Bhavan, M.P. Road, Mazgaon, Mumbai- 400010, and would start at 1030 Hrs. Tenderers are advised to formulate their views/queries in the form prescribed below in “**MS-WORD**” format and forward the same to The Managing Director, IPGL, on or before **09-03-2018** on e-mail md.indiaportsglobal@gmail.com, mt.indiaportsglobal@gmail.com indicating their intention to attend the pre-bid meeting. The prospective tenderers, who intend to attend the pre-bid conference, are required to submit authorisation letter from the tenderer for the representative attending the pre-bid conference. During the pre-bid meeting, the queries received in advance would be clarified first, followed by those submitted in writing, during the meeting. No further queries shall be entertained after the Pre-Bid Conference. The changes, if any, proposed by the Tenderer would be discussed and the Port Trust's response would be provided to all the Tenderers. The queries received from all the prospective Tenderers would be consolidated and IPGL's response to the same would be communicated to all the Tenderers in writing (through e-mail) well in advance to the last

date of submission of tenders. The clarifications so issued would form part of the tender and remain binding on all the Tenderers which shall be accepted and submitted by all the Tenderers along with their offer, duly signed by the authorised signatory on each page.

Format for sending queries:

Sr. No.	Clause No.	Tenders Specification Requirements	Queries	Clarification From IPGL
---------	------------	------------------------------------	---------	-------------------------

2.18 TENDER OPENING AND EVALUATION

2.18.1 OPENING OF TECHNICAL BID:

Technical Bids of the tender, received up to closing time on stipulated date, shall be opened on the same day i.e. 10-04-2018 at 1530 Hrs at Conference Hall, IPGL, Nirman Bhavan M.P. Road, Mazgaon, Mumbai- 400010 in presence of Tenderers' duly authorised representative, who may wish to be present. The Tenderer -representatives who are present shall sign a register evidencing their attendance. Tenders shall be opened as per the following procedures:

- a) In the first instance the envelopes containing cost of tender document for the tenderers who have downloaded the tender document from web site will be checked and opened. Then the envelope containing covering letter and confirmation of submission of the tender as required (Envelope - 1) and EMD (Envelope -2) shall be opened and checked.
- b) Thereafter the Letter of application cum Tender form and Technical Bids i.e. Volume I of the tender document (Envelope -3) of those tenderers whose tenders are accompanied by EMD shall be opened. At the time of opening only the contents of the covering letter and salient details of Technical Bids as considered appropriate by the tender- opening Officers shall be read out.
- c) The **envelopes containing the Price Bid i.e. Envelope 4, shall not be opened.** All the sealed Price Bids of the Tenderers shall be put in separate cover and sealed in presence of the Tenderer's representatives. The sealed cover containing Price Bids shall be kept in the safe custody of IPGL to be opened at subsequent date as per the procedure.

2.18.2 SCRUTINY AND EVALUATION OF THE TENDERS

- a) In the first instance the documents submitted with the Technical Bid will be scrutinised to ascertain whether the Tenderer fulfils the requirements as stipulated in the Minimum Eligibility Criteria Clause 2.1.1. The tenderer who do not fulfil the Minimum Eligibility Criteria shall not be considered for further evaluation
- b) The Technical Bids of the tenderers who fulfil the Minimum Eligibility Criteria at Clause 2.1.1 shall be thereafter scrutinised for responsiveness. For this purpose, a tender shall be treated as substantially responsive which meets with the all requirements of the tender documents and is without any deviations.

- c) After the tender opening, the whole process involving scrutiny, clarifications, evaluation and comparison of tenders and recommendations regarding award of Contract shall be confidential. Any efforts on part of any Tenderer to influence the IPGL or any officials in any way in the process of scrutiny, evaluation, comparison of tenders and decision concerning award of Contract may result in rejection of the Tenderer's bid.
- d) To assess the scrutiny, evaluation and comparison of tenders, the IPGL may ask Tenderer individually for clarifications. Request for clarification and response thereto, shall be in writing or through FAX or e-mail followed by post or through speed post. No change in Price or substance of the tender shall be sought, offered or permitted nor is the Tenderer permitted to withdraw the tender before the expiry of the validity period of the tenders in the process of clarifications.

2.18.3 OPENING OF PRICE BID

- a) Tenders, which are found to be in conformity with IPGL's Tender requirement and are considered substantially responsive, shall be considered for opening of Price Bid.
- b) The Tenderers found to be responsive shall be informed about the date and time of opening of their Price Bids. On the stipulated date and time the Price Bids of such Tenderers who are found to be responsive, shall be opened in the presence of authorised representatives of such Tenderers who wish to remain present.
- c) The Comparison and Evaluation of Price Bid for the award of contracts will be based on the lowest of the total landed cost of the Equipment quoted by the Tenderers covering CIF Price of the equipment (Yard Cranes) for Design, Manufacture, Supply, including, transportation, transit/Marine insurance, Assembly, testing, commissioning and other cost involved for making the equipment/items available at site till it is handed over at site, including insurance as per tender, price quoted for imparting necessary operational & maintenance training to IPGL personnel as per conditions of the Contract, cost of O & M Manuals and Training Manuals as per conditions of the Contract, warranty service during **2 years guarantee period and cost of maintenance tools etc. as per Schedule 10 B**, excluding the cost of spare-parts and special tools (optional and not taken for evaluation) enlisted under **Schedule 10**.
- d) The Tenderer whose bid is accepted by the IPGL shall be duly informed in writing. Within 15 days of receipt of intimation, regarding acceptance of its bid i.e. **Letter Of Acceptance (LOA)**, the Tenderer shall submit draft Contract Agreement and draft Bank Guarantee in the format approved by the IPGL as in the **ANNEX IV and V (Volume -I of Tender Document)**, and within 30 days the Contract agreement shall be signed between the IPGL and successful Tenderer. The successful tenderer shall submit performance bank guarantee as per Clause **3.39 (Volume-I)** of the tender document and **Annexure-V**. Concurrent with signing of the contract.

- e) The Tenderer whose offers are found not in conformity with the conditions of the tender, will not be considered for opening of price bids and their un-opened price bids will be returned after award of work to the successful tenderer.

2.19 NOTIFICATION AND AWARD OF CONTRACT:

Prior to the expiry of the prescribed period of tender validity or such extended time, the IPGL shall notify the successful Tenderer with **Letter of Acceptance (L.O.A.)**, by a FAX, e mail followed by registered letter that his tender has been accepted. The notification of award shall constitute the formation of the Contract. The successful tenderer, at his cost shall prepare and submit to IPGL five bound sets containing their technical offer and the various documentary transactions taken place between the employer and tenderer till the finalisation and award of the Contract.

2.20 Export Approval

This contract will be subject to the respective export approval laws of country of origin.

3. GENERAL CONDITIONS OF CONTRACT

3.1 DEFINITION AND INTERPRETATIONS:

In the Contract, as hereinafter defined, the following words and expressions shall have the meanings hereby assigned to them except where the context otherwise requires:

- 3.1.1 “IPGL” or “Employer” or “Company” means Board of Directors of India Ports Global Private Limited, a company incorporated on 22nd January, 2015, under Indian Company Act 2013, which herein after may be referred to also as “IPGL” (India Ports Global Limited).
- 3.1.2 “Contractor” means the firm, corporation or company whose tender has been accepted by the IPGL and includes the Contractor’s servants, Authorised Distributor / Dealer / Licensee, and workmen, personal representatives, successors and permitted assigns.
- 3.1.3 “Sub-Contractor” shall mean a person or persons to whom a part or full portion of the work has been assigned by the Contractor with information to IPGL in writing.
- 3.1.4 “Contract” means and includes Tender Documents, Instructions to Tenderers, General Conditions of Contract, special conditions, if any, drawings, specifications, Price Schedule and other annexure and Schedules etc., any amendments/clarifications thereto, Letter of Acceptance (LOA) and the Contract Agreement entered into between the IPGL and the Contractor as per format given in Annex- IV of the tender document.
- 3.1.5 “Contract Price” means the sum named in the Letter of Acceptance subject to such additions thereto, or deductions there from, as may be made under the provisions of the Contract.
- 3.1.6 “Specification” means the specification referred to in the Tender document and any modification thereof or addition thereto as may from time to time be furnished or approved in writing by the Employer.
- 3.1.7 “Site” means the land and other areas on, under, in or through which the Works are to be executed or carried, or any other places provided by the Employer for the purpose of the Contract.
- 3.1.8 “Works” means Design, Manufacture, supply, Installation, Testing, Commissioning & Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton. Capacity Yard Cranes to be supplied at Multipurpose Terminal, India Ports Global Ltd, Shahid Behesti Port, Chabahar.
- 3.1.9 “Approved/Approval” means the approval in writing.
- 3.1.10 “Engineer-In-Charge” means the Project Manager, IPGL, or any officer authorised.
- 3.1.11 “Drawings” means the drawings referred to in the Specification and any modification of such drawings approved in writing by the Engineer- In – Charge and such other drawings as may from time to time be furnished or approved in writing by the Engineer-In-Charge or any officer authorised
- 3.1.12 “Schedule” shall mean the schedule annexed to the tenderers bid.
- 3.1.13 “Tests on completion” shall mean such tests as are prescribed by the applicable Design Standards (latest editions), codes and described in the tender document, to be made by the Contractor before the equipment/items are supplied, delivered and taken over by the Employer.
- 3.1.14 “Writing” shall include any manuscript, typewritten or printed statement under or over signature and seal as the case may be.

3.1.15 "Defect Liability Period" has the meaning assigned in the clause no. 3.29 of the tender document (Vol.I).

3.1.16 "Month" means calendar month.

3.1.17 "Day" means calendar day.

3.1.18 "Letter of Acceptance" means the formal acceptance, made by or on behalf of the Employer, of the tender including any clarifications/amendments/adjustments or variations to the tender agreed between the Employer and the Contractor.

3.1.19 "Foreign currency" means the currency other than Indian Currency.

3.1.20 "Commissioning of Equipment" has the meaning assigned in clause no.3.37 of the tender document (Vol.I).

3.2 SINGULAR AND PLURAL:

Words implying the singular only also include the plural and vice versa where the context required.

3.3 HEADINGS OR NOTES:

The headings in these conditions of Contract and instructions to tenders shall not be taken to be part thereof, or be taken into consideration in the interpretation, or construction thereof, or of the Contract.

3.4 ENGINEER-IN-CHARGE AND HIS REPRESENTATIVE

3.4.1 The Engineer-In-charge shall carry out such duties in issuing decisions, certificates and orders as are specified in the Contract.

3.4.2 The Engineer-In-charge may from time to time, in writing delegate to his Representative any of the powers, discretion, function and/or authorities vested in him and he may at any time revoke any such delegation. Any written decision, instruction or approval given by the Engineer In Charge to the Contractor in accordance with such delegation shall bind the Contractor provided always that:

a) Any failure of the Engineer In Charge to disapprove any Plant/ workmanship shall not prejudice the power of the Engineer In Charge thereafter such plant or workmanship and to order the rectification thereof in accordance with these conditions;

b) If the Contractor shall be dissatisfied by reason of any decision of the Engineer In Charge he shall be entitled to refer the matter to the officer above the rank of Engineer In Charge who will thereupon confirm, reverse or vary such decision.

3.4.3 Wherever by these conditions the Engineer-In-charge is required to exercise his discretion, by giving a decision, opinion, consent or to express satisfaction or approval, or to determine value or otherwise take action which may affect the rights and obligations of the Contractor, the Engineer- In-charge shall exercise such discretion fairly within the terms of the Contract and having regard to all the circumstances. If either party disagrees with the action taken by the Engineer-In -Charge he shall be at liberty to refer the matter to Appellate Authority with these conditions.

3.5 OBLIGATIONS OF THE CONTRACTOR

3.5.1 The Contractor shall exercise all reasonable care and diligence in the discharge of all technical, professional and Contractual duties to be performed by them under this Contract as specified in the

Scope of Work within the Time for Completion and provide all labour, including the supervision and security thereof, Contractor's Equipment necessary thereof and for carrying out his obligation, so far as the necessity for providing the same is specified in or is reasonably to be inferred from the Contract. The Contractor shall be fully responsible to the IPGL for proper, efficient and effective discharge of their duties.

3.5.2 Contractor shall furnish bond in the form of Bank Guarantee towards the performance of the work as per clause 3.39 (Volume-I) of this tender document.

3.5.3 If the Employer shall consider himself entitled to any claim under the performance Guarantee he shall forthwith so inform the Contractor specifying the default of the Contractor upon which he relies. If the Contractor fails to remedy such default within 30 days after the receipt of such notice the Employer shall be entitled to forfeit to the extent of the loss or damage incurred by reason of the default.

3.5.4 The Contractor shall proceed with the Works in accordance with the decisions, instructions and orders given by the Engineer In-Charge in accordance with the condition of the Contract.

3.6 ASSIGNMENT AND SUBLETTING

3.6.1 The Contractor may sub let the Works or any part thereof with prior intimation and approval from the Employer.

3.6.2 He shall neither assign his right and interest in these presents tender nor assume a fresh partner or partners, or dissolve the partnership existing between him in reference to this Contract without the written permission of the IPGL

3.6.3 In the event of any activity being sub-contracted, the total liability and responsibility for meeting obligations and performance under Contract agreement shall rest with the Contractor. In the event of the Contractor contravening this condition, the Port shall be entitled to terminate the Contract forthwith and award a fresh Contract to some other party at risk and cost of the Contractor who shall be liable for any loss or damage which IPGL may sustain in consequence arising out of such replacement of the Contractor. In such case the performance guarantee shall be forfeited.

3.6.4 Such consent, if any, shall not relieve the Contractor from any liability or obligations under the Contract and he shall be responsible for the acts, defaults and neglects of any Sub-Contractor or his servants, Authorised Distributor / Dealer / Licensee, or workmen fully if they were the acts, defaults or neglects of the Contractor provided always that the provisions of labour or a piecework basis shall not be deemed to be sub-letting under this clause.

3.7 PATENT RIGHTS:

3.7.1 The Contractor shall fully indemnify the Employer against any action, claim or demand, costs or expenses arising from or incurred by reason of any infringement or alleged infringements of letters, patents, Design, trademark or name, copyright or other protected rights in respect of any machine, plant, work, materials or things, system or methods of using, fixing working or arrangement used for fixed or supplied by the Contractor in India, or elsewhere.

3.7.2 All payments, or otherwise shall be deemed to be included by the Contractor in the Prices named in the tender and shall be paid by him to whom they may be payable.

- 3.7.3 In the event of any claim being made or action brought against the Company in respect of any such matter as aforesaid, the Contractor shall be immediately notified thereof and he shall, with the assistance if he so requires of the Company, but at the sole expense of the Contractor, conduct all negotiations for the settlement of the same or any litigation that may arise there from, provided that the conduct of such negotiations or litigations shall be conditional upon the Contractor giving to the Employer such security as shall from time to time, reasonably required by the Employer to recover the ascertained or agreed amount as the case may be of any compensation, damages, expenses and cost which might be payable by IPGL in respect of or as result of any negotiation or litigation.
- 3.7.4 Intellectual property rights developed by seller shall remain with him and buyer shall not claim any right of business on the same.

3.8 GENERAL OBLIGATION OF THE EMPLOYER

In execution of the Works no person other than the Contractor, sub Contractors and his and their employees shall be allowed on the site except by the written permission of the Engineer In Charge or his authorised representative, but the Engineer in charge, his authorised representative, other authorities and officials of the Employer shall be afforded to inspect all facilities arranged by the Contractor at site.

3.9 CUSTOMS DUES, PORT DUES etc.

- 3.9.1 In case Contractor brings in any special tools or material for commissioning of the Cranes (as appearing in the price schedule), the contractor shall pay all applicable duties in respect of any such materials to be imported/exported to/from destination port.
- 3.9.2 It shall be the responsibility of the successful Contractor to comply with all the required formalities for custom clearance for items stated in CL 3.9.1, at destination port and pay the charges as applicable and take necessary clearance required from the customs department.
- 3.9.3 Custom clearance for items appearing in the price schedule of this tender document and associated custom duty (if any), shall be the responsibility of IPGL. However the Contractor will provide all support / documents, as required.
- 3.9.4 If available, Office space including electricity and water, as indicated by the tenderer shall be Provided on chargeable basis.
- For avoidance of doubt:
- (i) It is further clarified that CIF value includes all dues at port of origin and vessel related charges at disport, including insurance till receipt of equipment at disport.
 - (ii) Wharfage at disport (if applicable) will be reimbursed to the bidder against the documentary evidence.
 - (iii) Taxes and duties for those items / equipments which are appearing in the Price Schedule, the custom duty at the destination port shall be borne by IPGL.

3.10 SHIPMENT:

- 3.10.1 In case of a foreign shipper, the shipment of the consignment shall be arranged by the Contractor, subject to applicable export approval laws of country of origin.
- 3.10.2 It is necessary that adequate notice have to be given to the authorised forwarding agent regarding readiness of the cargo for the shipment.
- 3.10.3 The Bill of Lading should be drawn so as to show:
 - 3.10.4 Shippers: Tenderer's Nominee
 - 3.10.5 Consignee: India Ports Global Ltd or its SPV.
- 3.10.6 The Contractor shall submit shipping list to the IPGL for information.
- 3.10.7 The Bills of Lading (clean and shipped on board) should be made to order and bank endorsed. A copy of bill of lading should be sent to IPGL.
- 3.10.8 Import permission, if required, at the port of destination will be obtained by IPGL on request from the supplier prior to shipment/delivery.

3.11 PACKING AND MARKING FOR SHIPMENT:

- 3.11.1 All equipment/spare parts required under this Contract shall be packed, securely placed and protected by the Contractor during transportation to destination port. Packing cases shall be of a size convenient for shipment for cases containing easily damageable articles. The Contractor will be held responsible for the improper packing and protection of the parts.
- 3.11.2 The cases, crates and packages shall be permanently branded and painted with the shipping marks. The marking shall be carried out with a view to the mark remaining unobliterated, when the consignment reaches destination but as a further precaution, a reproduction of the shipping marks shall be placed inside each case, crate and packages.
- 3.11.3 Packages or bundles, which cannot be permanently branded, shall have metal label, with the above particulars stamped or attached to them by strong wire.
- 3.11.4 Yard Cranes shall be supplied in fully erected and pre tested condition. However the bidder shall have the option of on-site erection delivery method. In any case, this bidder should ensure that the most economical offer considering the overall timeline of supply of equipments shall be provided in the Price Offer. Alternate price offer shall not be allowed.

3.12 COMPLETION PERIOD OF WORK:

Under this tender IPGL intends to invite price offer for acquiring 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton capacity Yard Cranes at Shahid Beheshti Port, Chabahar.

The period of completion for total Works, under this Contract shall be as given below:

Name of the work: "Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All-Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain

60 Ton capacity Yard Cranes at Shahid Beheshti Port, Chabahar With a Total completion period of **9 (Nine)** months from the date of opening of Letter of Credit (LC), whichever is acceptable both sides.

3.13 RATES AND AMOUNTS INCLUDE ALL CHARGES:

The rates and amounts submitted by the Tenderer shall include all payments on account of taxes, levies, duties, royalties etc. as applicable and payable in the country of origin including all incidental charges that the tender may to bear for the execution of works.

3.14 ADDITIONS AND ALTERNATIONS:

3.14.1 IPGL may give instructions and directions as may appear (necessary and proper) to the IPGL for the guidance of the Contractor and good and efficient execution of the Works under this contract without altering major conditions and scope of work of the Contract.

3.14.2 The Contractor shall receive, obey and be bound by the same according to the true intent and meaning thereof.

3.15 EXECUTION:

The Contractor shall, in consideration of payments to be made to him as hereinafter provided, execute and do the Works set forth as described in the scope of the work and specifications, including any amendments to tender clauses.

3.16 EXTRAS:

Any extra expenses incurred in connection to the Works by the IPGL in the performance of the Works owing to the neglect or omission on the part of the Contractor, in any of the case mentioned in this Contract shall be deducted from any sum due or which may thereafter become due to the Contractor or from any amount lying with them or under their control or he may be called upon to pay the amount of such extra expense to such person or persons as the IPGL may appoint to receive the same and in the event of the Contractor failing to make such payment, the said amount shall be recoverable from him in such manner as the IPGL may determine.

3.17 USE OF GROUND:

The Contractor shall be allowed to use such an area as in the opinion of the IPGL may be absolutely necessary for the proper and efficient execution of Works and on completion of Works or termination of his Contract, he shall clear away all his tools, plant, rubbish and other materials within a fortnight and hand over vacant and peaceful possession of the same to the IPGL in a tidy and clean condition. The Contractor shall not be allowed to erect any structures on any property of the IPGL.

3.18 CONTRACT DOCUMENT MUTUALLY EXPLANATORY:

- 3.18.1 The several documents forming the Contract are to be taken as mutually explanatory of one another and should anything appear in one that is not described in the other, no advantage shall be taken of any such omission.
- 3.18.2 In case of any discrepancies or inconsistencies however appear, or should any misunderstandings arise as to the meaning and of the specifications or drawings or as to the dimensions or the quality of the material or proper execution of the Works or as to the measurement or quality and valuation of the Works executed under this Contract or as extra thereupon, the same shall be explained by the Engineer-in-charge or his authorised representative.
- 3.18.3 The explanation of Engineer-in-charge or his authorised representative shall be final and binding upon the Contractor and the Contractor shall execute the Works according to such explanations, and without extra charge or deductions to/from the Prices specified in the bill of quantities and do all such Works and things as may be necessary for the proper completion of the work as implied by the specification and drawings, even though such work and things are not specifically shown and described therein.

3.19 ACCESS TO SITE:

The Contractor shall obtain prior permission of the IPGL before any person connected with the Works visits the site. The Contractor shall abide by the regulations and rules of India Ports Global Ltd /Security agency at destination port in respect of entry/exit and movement in the premises and any other directives issued by the Government / Statutory Agency from time to time during execution of the contract.

3.20 CONTRACTOR'S EQUIPMENT:

- 3.20.1 The Contractor shall be responsible for supply, use and maintenance of all the equipment and he shall ensure that they are suitable for the work and are maintained in such a manner as to ensure their efficient working.
- 3.20.2 IPGL may, if they deem fit, direct the Contractor to remove from site any equipment which are not efficient and/or prejudicial to the quality of the work to be replaced by equipment to their satisfaction. The Contractor shall immediately follow IPGL's directions/instructions.

3.21 EXISTING SERVICES:

- 3.21.1 Drains, pipes, cables, overhead wires and similar services whether above or below the ground which may be encountered in the course of the Works shall be saved and kept harmless from injury and/or loss or damages by the Contractor at his own costs and expenses so that they continue to be in full and uninterrupted use to the IPGL.
- 3.21.2 The Contractor shall not store any materials or otherwise occupy any part of the site in a manner likely to hinder the operation of such or any services. The Contractor shall at his own costs and expenses and without any delay repair and make good to the satisfaction of the Employer, any injury and/or loss or damage caused by the Contractor to the same.

3.22 LABOUR:

- 3.22.1 In case required, the Contractor shall make his own arrangements for the engagement of all labour for doing the work, at site or in respect of or in connection with the execution of work as also for the transport, housing, feeding and payment thereof. Since time is the essence of this Contract, requisite number of labour force has to be kept, so as to complete the Installation, Testing and Commissioning of the equipment within the completion period as stipulated in the tender.
- 3.22.2 In the event of any outbreak of illness or an epidemic nature, the Contractor shall comply with and carry out such regulations, orders and requirements as may be made by the Government, or the local medical or sanitary authorities for the purpose of dealing with and overcoming the same.
- 3.22.3 The Contractor shall at all times take all reasonable precautions to prevent any unlawful, riotous or disorderly conduct by or amongst his employees and for the preservation of peace and protection of persons and property in the neighbourhood of the Works against the same.
- 3.22.4 The Contractor shall at all times during the continuance of the Contract comply fully with all existing Acts, Regulations and bye law as including all statutory amendments and re-enactment of state, Central Government authorities and other local authorities and any other enactment and acts that may be passed in future either by the State or the Central Government or local authority, including Labour Laws, Factories Act, Minimum Wages Act etc
- 3.22.5** If as a result of Contractor's failure, negligence, omission, default or non-observance of any provisions of any laws, the IPGL is called upon by any authority to pay or reimburse or required to pay or reimburse any amount, the IPGL shall be entitled to deduct the same from any moneys due or that they become due to the Contractor under this Contract or any other Contract or otherwise recover from the Contractor any sums which the IPGL is required or called upon to pay or reimburse on behalf of the Contractor. All registration and statutory inspection fees in respect of his work pursuant to the Contract shall be paid by the Contractor.
- 3.22.6** The Contractor shall pay the labourer engaged by him on the work not less than a fair wage, which expression shall mean, whether for time or piece work, rate of wages as may be fixed by the relevant statutory authority as fair wages for payable to the different categories of labourers or those notified under the Minimum Wages Act or applicable local laws of the respective country.
- 3.22.7 Safety Gears Etc.:** The Contractor shall at his own expenses provide all safety gears for all labours engaged during the work and failing to do so, IPGL shall provide the same and recover the cost thereof from any amount due or which may become due to the Contractor or from any amount lying with them or under their control.

3.23 PLANT AND EQUIPMENT:

The Contractor shall at his own costs and expenses provide all labour, plant, haulage, transportation of plant and equipment to be used for executing the Contract, all materials, stores etc required for efficiently carrying out and completing the work to the satisfaction of the IPGL.

3.24 INSPECTION AND TESTING OF WORK AT CONTRACTOR'S AND SUB CONTRACTOR'S

PREMISES:

- 3.24.1 The Engineer In-charge or his Representative shall have at all reasonable time access to the Contractor's and sub-contractors premises/work site and shall have the power at all reasonable time to inspect, examine and test the materials & workmanship of the work during its Manufacture. The employer shall depute two engineers for inspection & testing at contractor's works and sub contractor's premises for maximum 5 days, for which the necessary co-ordination & arrangements shall be made by the contractor at his cost. The contractor shall give at-least 30 (thirty) days' advance notice to the Engineer-In-Charge for each pre-shipment inspection.
- 3.24.2 The expenses of two engineers deputed for inspection of cranes to contractor's work shall be deemed to be included in the price of equipment. i.e. travelling from Mumbai to contractor's works and back, lodging & boarding, transportations at contractor's works etc.
- 3.24.3 The Engineer In-charge or authorised representative during such inspections shall be at liberty to reject all or any materials of workmanship in the subject of any of the said grounds of objection which are not in accordance with the Contract.
- 3.24.4 In all cases where the Contract provides for tests whether at the premises of the Contractor or any sub-Contractor or elsewhere, the Contractor except where otherwise specified shall provide free of charges such labour, materials, electricity, fuel, water, stores, apparatus and instruments as may reasonably be demanded, to carry out sufficiently such tests of the work in accordance with the Contract and shall at all time facilitate the Engineer In-charge and his assistant to accomplish such Testing.
- 3.24.5 The cost of all tests and/or analysis affected at the Contractor's or sub- Contractor's work and on the installation site shall be borne by the Contractor. The cost of independent test and/or analysis which the Engineer In-charge or his authorised representative may cause to be made and which prove satisfactory shall be borne by the Contractor and also the Contractor will be called upon to pay all expenses incurred by the Employer in respect of any work found to be defective or of inferior quality, adulterated or otherwise unacceptable.
- 3.24.6 Third Party Inspecting Agency (internationally accredited) shall certify the Yard Cranes before shipment at Contractor's site. The third party inspection would be limited to the pre dispatch inspection /load test. They will also witness, the materials as per scope of supply, painting of the crane and will sign the "ready to ship" document. The cost of such inspection would be included in the price. The Contractor shall give the Engineer In-charge such reasonable notice of the progress of the work and shall intimate the tentative date of shipment & arrival at IPGL well in advance. The contractor shall furnish a certificate issued by Third Party Inspection Agency towards "Ready to ship" prior to transportation of Yard Cranes from contractor's works.
- 3.24.7 The Yard Cranes without inspection, examination and Testing shall not be prepared for shipment or transportation, as the case may be, without the consent of the Engineer In-charge, as being ready for shipment or transportation. Such passing or consent shall not relieve the Contractor from the liability to complete the Contract Works in accordance with the Contract.

- 3.24.8. If cranes are assembled on site then contractor at his own cost is required to submit a certificate from Third Party Inspection Agency (should be a reputed international accredited agencies) to IPGL Certifying that the equipment is meeting the technical requirements of the tender.

3.25 TESTING OF EQUIPMENT AT CONTRACTOR'S AND EMPLOYER'S SITE

- 3.25.1 The tests at Contractor's site shall include operational and capacity tests. The capacity test for hoist motion shall be with an overload of 10% in excess of the rated working load. The date for operational and capacity test shall be set by the Contractor and shall be informed to Engineer-In-Charge in advance. The Contractor shall be responsible for any adjustments or corrections found necessary during the test. In case of any damage during transit, the same load test to be carried out in presence of TPIA at IPGL site at contractor's risk and cost.
- 3.25.2 The Contractor shall arrange to test the equipment for load test by a Competent Agency notified by competent authority at Employer's site and submit the certificate to this effect to the Engineer-In-Charge. The test load required shall be arranged by IPGL. The contractor shall produce the certificates issued by the competent authority for these test load / containers being used for load test at site.
- 3.25.3 Adequate strength of qualified & experienced engineers shall be deputed at work site to attend recurring faults on advice of the Engineer in Charge during the testing, commissioning & warranty period. The cost of the same shall be deemed to be included in the quoted price.

3.26 DRAWINGS:

The Tenderer shall submit along with the tender, one copy of the Operational and Maintenance Manual, which must include the following:

- 3.26.1 General arrangement of the crane offered with principal details and leading dimensions etc.
- 3.26.2 Schematic electric, electronic and programmable controller details.
- 3.26.3 Schematic arrangement of hoist & boom hoist wire ropes, Electric room and Machinery house arrangement etc.
- 3.26.4 General arrangement of the operator's cabin, clearly indicating the location of various controls and indicators.
- 3.26.7 All technical details of electrical infrastructure.

Note: All dimensions of the drawings shall be in Metric units and all writings shall be in English.

3.27 TESTS ON COMPLETION AT EMPLOYER'S SITE

- 3.27.1 On completion of fabrication of all items at the Contractor's premises and also when Installation/final adjustments at site are completed in accordance with the Contract, the Contractor shall give the Engineer In-charge notice in writing thereof and before making the tests on completion of 7 days'

notice in writing of the date on which he will be ready to make the said tests in accordance with and in the manner prescribed in the specifications.

- 3.27.2 The tests on completion shall be made on each item when final adjustments and tests are completed at the Contractor's premises in the presence of Engineer In charge or his authorised representative if desired necessary, in accordance with the Contract and also when erection/Installation is completed at IPGL site in accordance with the Contract.
- 3.27.3 If any portion of work fails under the tests to fulfil the Contract conditions, tests of the faulty portion shall, if required by the Engineer In-charge or by the Contractor, be repeated within reasonable time upon the same terms and conditions.
- 3.27.4 As per FEM, full load test has to be done at manufacturer's site in the presence of TPIA. If the crane shall be dismantled after full load test, a load test shall also be carried out at the IPGL site. The test shall be carried out by the Contractor at the time fixed by the Engineer In-Charge for the commencement of commercial operations and if in opinion of the Engineer In-charge the tests are being unduly delayed, the Engineer In-charge may, in writing, call upon the Contractor under three days notice to make such tests. The Engineer In-charge may proceed to make such tests himself, at the Contractor's risk and expense. If the crane is transported in fully erected condition, without dismantling, after the load test according to FEM standard is done at the manufacturer's work, then 2nd load test will not be required at IPGL site.
- 3.27.5 If the Contractor neglects to make the 'Performance test' (Acceptance Test) within the time stipulated by the Contractor, the Employer shall nevertheless have the right of using the Yard Cranes at the Contractor's risk until the 'Performance test' is successfully carried out.

3.28 REJECTION OF DEFECTIVE WORK:

- 3.28.1 If the complete erection/Installation at site or any portion thereof before being taken over, under Clause 3.30 (Volume-I of Tender Document) is defective, or fail to fulfil the requirements of the Contract, the Engineer In-charge shall give notice to the Contractor setting forth particulars of such defects and the Contractor shall forthwith make the defective supply/plant/ Installation good, or alter the same to make it comply with the requirements of the Contract.
- 3.28.2 If Contractor fails to do so within a reasonable time, IPGL may reject and replace the same at the cost of Contractor, the whole, or any portion of the work, as the case may be, which is defective or fails to fulfil the requirements of the Contract. The Contractor's full and extreme liability under this clause shall be satisfied by the payment to IPGL, the extra cost, if any, of such replacement delivered and erected. Such extra cost being ascertained shall be deducted from the Contractor's bill.
- 3.28.3 If any supply of defective items shall have caused delay in the completion of the Contract so as to give rise to a claim for damage on the part of the IPGL nothing contained in this clause shall interfere with or prejudice any rights of the Employer with respect to such claim.

3.29 DEFECT LIABILITY PERIOD

In this condition the expression 'Defect liability period' shall mean a period of **24months or 4000 hrs** of operation, calculated from the date of Final acceptance of the Crane, whichever is earlier.

3.30 DEFECTS AFTER TAKING OVER

- 3.30.1 The Contractor within 4 weeks from the date of communication by the Engineer In charge, shall be responsible for making good at his expense any defect in or damage to any portion of the Works which may appear or occur during the defect liability period and which arises either:
- a) From any defective materials, workmanship or Design or
 - b) From any act or omission of the Contractor done or omitted during the said period.
- 3.30.2 If any such defects shall appear or damage occur the Engineer- In –Charge shall forthwith inform the Contractor thereof stating in writing the nature of defect or damage. The provision of this clause shall apply to all replacements or renewals carried out by the Contractor to remedy defects and damage as if the said replacements and renewals had been taken over on the date they were completed to the satisfaction of Engineer In Charge. Replacements or renewals of parts shall be warranted for a period of 24 months or 4000 hrs of operation from the date of final acceptance of the crane, whichever is earlier.
- 3.30.3 If any such defect or damages were not remedied within a reasonable time, IPGL may proceed to do the work at the Contractor's cost & risk.

3.31 TIME OF ACCEPTANCE:

The supply, delivery and Installation of the equipment/ items at site shall be deemed to have been accepted by IPGL when the same shall have been installed, tested & commissioned and the Engineer-In-charge shall have issued the final acceptance certificate as per clause 3.35.4.

3.32 TERMS OF PAYMENT:

The payment due under this Contract shall be effected as per following;

Mode of Payment: The payment to the contractor for acquisition of the equipments under the contract shall be effected by IPGL through irrevocable letter of credit (L/C), which is acceptable to both sides, against stage-wise payments. The charges towards opening of L/C within India shall be borne by the Employer (IPGL) and charges towards opening of L/C outside India shall be borne by the Contractor. Any charges against extension of L/C for what-so-ever reason shall be borne by the Contractor, both in India and outside India.

(a) **First stage:** Initial advance up to **10 %** of CIF Price of equipment mentioned in the LOA against submission of a Bank Guarantee equivalent to 110 % of the advance amount and this initial advance will not carry interest. However, if the contract is terminated due to default of the contractor the initial

advance would be deemed as interest bearing advance at an interest rate of base Prime Lending Rate of SBI + 2 % p.a. to be compounded quarterly.

(b) Second stage: 60 % of CIF Price mentioned in LOA after **shipment of the equipment and submission of shipment documents of** satisfactory evidence of **shipment of** equipment.

Documents required for second stage payment:

- (i) Original clean and shipped onboard Bill of Lading, 3 copies
- (ii) Commercial invoice,(03) copies
- (iii) Certificate of origin,(03) copies
- (iv) Packing list for each Crane

Note: In case advance payment is not taken by the contractor, second stage payment after shipment of equipment as 70% can be claimed by the contractor.

(c) Third stage: 20 % of CIF Price mentioned in LOA against receipt of equipments at destination port in good condition.

(d) Fourth stage: 10 % of CIF Price mentioned in LOA after issuance of final acceptance certificate by the Engineer-In-charge for the Equipment, after completion of Commissioning of equipment and compliance of operation to endurance test activities and on verification and certification by Engineer-In-Charge against commissioning of equipment and handing over of the cranes for commercial operations.

Note: For the second, third and fourth stage payments, pro-rata payment shall be considered in case the contractor makes staggered delivery.

3.32.2 **Payments** towards Spare Parts / Tools as listed out at Schedule–10(Volume I), if applicable, shall be made in two stages as mentioned below;

A	50 % of CIF Price mentioned in the LOA against delivery of Spare parts and Special Tools as per the list attached at Schedule – 10 (Volume I) at Employers Main Stores duly certified by the Engineer – In -Charge for receipt of the same.
B	50 % of CIF Price mentioned in the LOA on commencement of commercial operation of the equipment.

Spare Parts as listed out at **Schedule– 10 (volume I)** are optional and not to be considered for evaluation. However, the bidder has to confirm that the prices quoted in the sealed price bid i.e. **Schedule 11Part II** for spares will remain valid for 2 years from the date of Final Acceptance.

3.32.3 **Payment for rendering Warranty Support:**

Charges for rendering Warranty Support as mentioned in the LOA shall be paid after satisfactory

completion of warranty period as per clause 3.58 of the tender and issuance of certificate by the Engineer-In-Charge.

IPGL will endeavor release of payment subject to compliance of required documents by the contractor, within 30 days.

3.32.4 Payment of Duties

It may be noted that Custom Duty at destination Port will be borne by IPGL on import of ONLY those items / equipment appearing in the Price Schedule of this tender document.

3.33 Payment of taxes and Levies:

3.33.1 The Contractor shall pay all taxes and levies as applicable and payable in the country of origin including all incidental charges that the tenderer may have to bear for the execution of works.

3.34 NO INTEREST ON ACCOUNT OF DELAYED PAYMENTS:

Any claim for interest will not be entertained by the IPGL with respect to any payment or balance which may be in their hands owing to any disputes between themselves and the Contractor or with respect to any delay on part of the IPGL in making payment.

3.35 CERTIFICATE AND PAYMENT

3.35.1 Certificate of payment

The Contractor may at the times and in the manner following apply for interim and final certificates as referred to in Clause 3.32 (Terms of Payment - Volume-I of Tender Document) for Yard Cranes shipped to the site and for work executed on the site.

3.35.2 Certificate for receipt of Equipment at site

Application for Certificate for receipt of Equipment at site may be made to the Engineer In Charge against arrival and safe unloading of cranes and spares at site, accompanied by certificate for ready to shipment issued by Third Party Inspecting Agency, inspection release note, certificate for receipt of all parts of entire equipment in safe condition at site by Third Party Inspection Agency, certificates from Marine Insurance Company(s)/other Insurance Company which covers all risks and other documents as the Engineer In Charge may reasonably require. Application shall state the amount claimed and shall set forth in detail, in the order of the schedule of Prices, particulars of the equipment received at the site along with declaration of the contractor to this effect. The Engineer In Charge shall issue to the Contractor a Certificate for receipt of Equipment at site within 14 days after receiving an application thereof.

3.35.3 Issue of Provisional Certificate:

Application for Provisional Certificate for satisfactory commencement of commercial operations of Equipment may be made to the Engineer In-Charge against release of equipment for commercial operations accompanied by undertaking that the pending punch list items shall be attended within 6 weeks from the date of this application. The Engineer In-Charge shall issue to the Contractor the

Provisional Certificate for Commercial Operations within 14 days after receiving an application thereof.

Subject to completion of requirements of clause 3.38 an application for Provisional Certificate for satisfactory commencement of commercial operations of Equipment may be made to the Engineer In-charge against release of equipment for commercial operations accompanied by undertaking that the pending punch list items shall be attended within 6 weeks from the date of this application. The Engineer In-charge shall issue to the Contractor the Provisional Certificate for Commercial Operations within 14 days after receiving an application thereof along with punch list. If any works related to safety of the equipment are balance to be attended then even though the cranes are in operation the same shall not be declared as commercial operation but under Trial operation and at the risk and cost of the contractor till issue of Provisional certificate by the Port for accepting the cranes for commercial operations. During such time of trial operations the Insurance risk of the cranes will be responsibility of the contractor.

3.35.4 Issue of Final Acceptance Certificate

Application for Final Acceptance Certificate of Equipment may be made to the Engineer In Charge against satisfactorily attending of punch list items and after the Contractor has ceased to be under any obligation under Clause 3.5 provided that, if a Provisional Certificate has been issued in respect of any Section or Portion of the Works, the Contractor may apply for a separate final certificate at any time after the said obligation has ceased in relation to such Section or Portion. Where the Contractor has carried out replacements or renewals to the Works in compliance with Clause 3.30 the Contractor's obligations shall continue, but the right of the Contractor to apply for a final certificate other than for the replacements or renewals shall not be affected by that fact and after the Contractor has ceased to be under any obligation under Clause 3.30 in respect of the replacements or renewals he may apply for a final certificate in respect thereof.

If the punch list items are attended within 6 weeks from the date of issue of provisional certificate, then the Final Acceptance Certificate shall be issued with effect from the date of issue of Provisional Certificate and in case the punch list items are completed beyond 6 weeks from the date of issue of provisional certificate, then the Final Acceptance Certificate shall be issued with effect from the date of Application for Final Acceptance Certificate after verification of completion of punch list items by Engineer In Charge. The Engineer In Charge shall issue to the Contractor the Final Acceptance Certificate within 28 days after receiving an application thereof.

3.35.5 Final Certificate conclusive

A final certificate shall, save in the case of fraud or dishonesty relating to or affecting any matter dealt with in the certificate, be conclusive evidence as to the sufficiency of the Works and of the value thereof unless any proceedings arising out of the Contract whether under Clause 3.50 & 3.51 (Arbitration Dispute Resolution- Volume-I of Tender Document) or otherwise shall have been commenced by either party before the final certificate has been issued or within three months thereafter.

3.35.6 Adjustment to Certificates

If any sum shall become payable to the Contractor under the Contract otherwise than for work executed or Yard Cranes delivered, the amount thereof shall be included in the next certificate (interim or final) issued by the Engineer In charge, and if any sum shall become payable under the Contract by the Contractor to the Employer, prior to the issue of the final certificate, whether by deduction from the Contract Sum or otherwise, the amount thereof shall be deducted in the next certificate.

3.35.7 **Corrections and with-holding of certificates**

The Engineer In-Charge may in any certificate give effect to any correction or modification that should properly be made in respect of any previous certificate. Engineer In-Charge shall have power to withhold any certificate if the Works or any part thereof is not being carried out to his satisfaction.

3.36 GUARANTEE PERIOD FOR NEW YARD CRANES:

3.36.1 The Yard Cranes to be supplied under this Contract shall be guaranteed for a period of **24 (Twenty Four) Months or 4000 hours** towards satisfactory performance of each components. The steel structures and paintings& anti-corrosions application shall be guaranteed for a period of sixty (60) months and thirty six (36) months respectively and same shall be in force from the date of final acceptance of the cranes, under this Contract, by the Engineer-In-Charge. The Contractor shall be responsible for any defects that may develop under proper use arising from faulty materials, Designs, workmanship in the work but not otherwise and shall at his own cost remedy such defects when called upon to do so by the Engineer In-Charge who shall state in writing in what respect any portion is faulty.

Note: Consumable items like lubricants, grease, filters for hydraulic system and for diesel engine are excluded under the guarantee period.

3.36.2 If it becomes necessary for the Contractor to replace or renew any defective portions of the supply of the items under this clause, the provisions of this clause shall apply to the portions of the supply so replaced or renewed component shall be under warranty till expiry of 12 months or 2000 hrs from the date of final acceptance of the crane whichever is earlier. If any defects are not remedied within a reasonable time, the Port may proceed to do the work at the Contractors' risk and expenses but without prejudice to any other rights, which IPGL may have against the Contractor in respect of such defects.

3.36.3 If the replacement or renewals are of such a character as may affect the efficiency of the items supplied, the Engineer In-charge shall have the right to give to the Contractor within one month of such replacement or renewal notice in writing the 'Test on Completion' be made in which case test shall be carried out as provided in Clause 3.27.4 (Volume-I). Costs of all the tests shall be borne by the Contractor.

3.36.4 All inspection, adjustments, replacement or renewal carried out by the Contractor during the period referred in this clause shall be subject to the conditions of this Contract which shall be binding on the Contractor in all respects during the guarantee period and extended guarantee period if any.

3.37 COMMISSIONING OF NEW EQUIPMENT (3 Nos. 100 Ton (AT) and 3 Nos. 60 Ton (RT) Capacity Yard Cranes):

3.37.1 Contractor shall complete the whole work such as Design, Manufacture, Supply, Installation, Testing and Commissioning of the cranes within a period stipulated in clause 3.12 (Volume-I), from the date of Opening of letter of credit (LC), which is actable both sides.

3.37.2 Contractor shall arrange to commission the equipment after due Testing and approval of the Engineer In-Charge within a minimum period from the date of Installation of the equipment at Employers' site and this period shall be considered within the total completion period stipulated in clause 3.12 (Volume-I) of Tender Document). All necessary testing materials, tools, slings etc. required for the Testing of the equipment shall be arranged by the Contractor at his own cost & risk. Since time is the essence of this contract, contractor shall ensure that requisite number of labour force / resources are made available at site, so as to complete the installation, testing and commissioning of all equipment at IPGL site within the completion period of the contract.

Note: If the crane is supplied in pre-erected condition and there is no damage during transit (as confirmed by TPIA / marine insurance company), the final load test at employer's site will be carried out on 2-3 preselected load parameters and will be witnessed by the local Competent Authority. Load for such test will be provided by IPGL. Such operational test can be taken as FAC if there are no punch items as stated below.

3.37.3 Commissioning of equipment shall mean handing over of equipment for regular operations after completion of performance test for all the parameters specified in the tender (Vol-II), without compromising safety norms and satisfying all functional requirements without affecting the productivity of the equipment.

- i. Any punch item which is not affecting safety norms and functional requirements without affecting the productivity of the equipment shall be closed within six weeks from the date of commissioning of equipment and put in regular commercial operations to consider the date of commencement of regular commercial operations as the date of acceptance of the equipment.
- ii. In case punch items are not closed within six weeks from the date of commissioning of the equipment, the date of closure of punch item shall be considered as date of acceptance. Defect liability period shall commence from the date of final acceptance of the equipment to be done.

3.38 REMOVAL OF MATERIAL ON COMPLETION (as applicable):

The Contractor shall, on completion of the Works or when directed by the Employer, remove all plant, equipment, tools, materials, temporary constructions etc. and rubbish which may have been accumulated during the execution of the work, other than those permanently used into the Works, at Employer's site.

3.39 PERFORMANCE GUARANTEE BOND TOWARDS PERFORMNACE OF CONTRACT

- 3.39.1 Within 45 days of the receipt of the notification of the award of Contract from the Employer, i.e. LOA, or 30 days from signing of contract between IPGL and contractor, whichever is earlier. the successful Tenderer shall furnish to the Employer, a bond in the form of a Bank Guarantee (B.G), from a Nationalised/ Scheduled Bank, having their branch in Mumbai, for an amount equivalent to **10% of the Contract Price** (as indicated in LOA) guaranteeing the performance of the Contract, as per the draft Bank Guarantee form at **Annex-V** of this tender document. The validity of such bank guarantee issued, towards performance of the Contract, shall be up to Hanover/FAC of cranes after successful completing all due tests/trials.
- 3.39.2 Failure of the successful Tenderer to submit the required Performance Guarantee shall constitute sufficient grounds for termination of the Contract & forfeiting the Earnest Money Deposit. The BG submitted towards performance shall be returned after deploying the cranes for regular operations and after receipt of performance BG towards defect liability period and upon making application thereof by the contractor.
- 3.39.3 **Performance Bond during Defect Liability period for new Yard Cranes:** After successful completion of the work, final Testing & Commissioning of the crane and before handing over of the new Yard Cranes supplied to IPGL under this contract, the Contractor shall submit a B.G, for an amount equivalent to 10% of the Contract Price towards guaranteeing the performance of the new cranes during defect liability period as per the draft Bank Guarantee form at Annex-V of this tender document. The validity of such bond issued shall be for a period of 12 months from the date of final acceptance certificate, with a claim period of 3 months thereafter. In this case, the para 1 of the BG format at Annex- V may be suitably worded indicating the work of contract for each capacity of new Yard Cranes only for this Guarantee.

Note: The tenderer has the option to submit only one Bank Guarantee covering Performance Bank Guarantee as well as warranty period (defect liability period), with a claim period of three (03) months, after completion of warranty.

- 3.39.4 **Performance Bond after completion of Defect Liability period for new Yard Cranes supplied:** The contractor shall submit a Performance Bond, in respect of new Yard Cranes supplied under this contract in the form of B.G for an amount equivalent to 3% of the Contract Price, towards performance of steel structures and painting, at least 30 days before the expiry of validity of bond mentioned under clause 3.40.3 (Volume-I of Tender Document) as per the draft Bank Guarantee form at Annex-V (Volume-I) of this tender document. The validity of this bond shall be for a period of 36 months, after defect liability period, with 3 months claim period thereafter. In this case, the para 1 of the BG format at Annex- V may be suitably worded indicating the work of contract for 3 Nos. of 100 Ton (AT) and 3 Nos. of 60 Ton (RT) capacity Yard Cranes as applicable only for this Guarantee.

3.39.5 In the event of failure of Contractor to ensure the performance of the equipment, during the guarantee period and not responding to the requirement of the situation as indicated in clause 3.37 (Volume-I of Tender Document), of this tender document and if the Employer is compelled to encash the B.G to meet the situation, the Contractor shall revalidate the said guarantee for the suitable period as agreed by the Employer.

3.39.6 The bond submitted by the Contractor towards the performance of the equipment during defect liability will be returned to the Contractor after successful completion of the defect liability period, to the satisfaction of the Employer and on making an application thereof and submission of Bank Guarantee as per clause 3.40.4.

3.40. SECURITY DEPOSIT TOWARDS ADVANCE PAYMENT FOR OF CONTRACT (i.e. NEW YARD CRANES):

3.40.1. The successful Tenderer shall furnish to the Employer, a security deposit in the form of a Bank Guarantee (B.G) from a Nationalised/Scheduled/International Bank, covered under section 2 (e) of the Reserve Bank of India Act 1974, having their branch in Mumbai for an amount equivalent to 110% of the advance amount to be made to the Contractor, for advance payment. Such B.G shall be as per the draft Bank Guarantee form at Annex-VI (Volume-I) of this tender document, applicable for the first stage payment at clause 3.32. 1 A

3.40.2 The Employer shall release advance as indicated in clause 3.32 (Volume-I), Terms of Payment, of this tender document to the Contractor against submission of Security deposit in the prescribed form.

3.40.3 The B.G issued, towards security deposit of advance payment, shall be valid till receipt of equipment at destination port. The B.G. submitted by the Contractor under clause will be returned to Contractor on making an application thereof.

3.40.4 In the event of failure of Contractor to complete the work within stipulated period, the Contractor shall revalidate the B.Gs for an extended period as agreed by the Employer however this will not relieve the Contractor from the obligation of penalty for delays as indicated in clause 3.43 (Volume-I) of this tender document.

3.41 FORFEITURE OF SECURITY DEPOSIT

IPGL shall be entitled to encash the Bank Guarantee deposited by the Contractor / Contractors with IPGL in the following event.

- a) In case of failure on the part of the Contractor/ Contractors, at any time, during the continuance of this Contract, to comply with any of the conditions herein contained, or
- b) In case of any breach of any portion of this Contract.

3.42 INDEMNITY:

3.42.1 Notwithstanding that all reasonable and proper precautions may have been taken by the Contractor at all times during the progress of the work, the Contractor shall nevertheless be wholly responsible for all damages, whether to the Works themselves or to any other property of IPGL, or to the lives, persons, property of others during the progress of the work.

3.42.2 In case any damage occurs to the existing structure due to the Contractor's operation, the same shall be made good by the Contractor at his own risk and cost. The areas, which are likely to be unsafe for use, shall be barricaded and all the necessary precautionary measures like displaying notices shall be taken by the Contractor, during Commissioning and Testing of equipment at site.

Further, it is clarified the Contractor shall not be liable for incidental, indirect or consequential damages to the extent such limitation of liability is valid under Indian Law.

3.43 Penalty for delays in completion of work.

- a) The Contractor has to Design, Manufacture, Supply, Install, Test, Commission and hand over the new equipment within the completion period as stipulated in **clause 3.12 (Volume-I of Tender Document)** from the date of opening of LC (acceptable to both sides) or such extended period as granted by IPGL. Time from receipt of equipment at the destination port till custom clearance by IPGL, will not be counted in the completion period.
- b) In the event of failure on the part of the Contractor to commission the new equipment for any reason whatsoever within the stipulated period as mentioned above, an amount of Euros per day shall be levied for delayed period as penalty as stipulated below in (e) for the work of Design, Manufacture, Supply, Install, Test, Commission and hand over the new Yard Cranes at Shahid Beheshti Port, Chabahar.
- c) The completion period of the contract will count from the date of letter of Credit(LC). The penalty for delays shall be levied for the delay beyond the scheduled date of delivery.
- d) Delay penalties shall be recovered in the currency of bid.
- e) Except as provided in the Cl. no. 3.53 of GCC (Force Majeure), if contractor fails to deliver any or all of the Goods by the Date(s) of delivery or perform the Related Services within the period specified in the Contract, the Employer may without prejudice to all its other remedies under the Contract, deduct from the Contract Price, as penalty for delays, a sum equivalent to **0.5 %** per week or part thereof, of the delivered price of the delayed Goods for each week or part thereof of delay until actual delivery, up to a maximum deduction of the percentage of **5 %** of Total Contract Price, However in case of part delivery or staggered delivery under Option 2 of Clause 3.12, penalty for delays of **0.5 %** per week or part thereof, shall be calculated based on the delivered price of balance/ un- fulfilled portions of the contractual obligations i.e. not delivered/not performed related service to the Employer (IPGL). This does not absolve the contractor from his obligation of completion of whole of the work in an expeditious manner. Contract price shall be inclusive of CIF price plus all taxes and duties payable for not delivered/not performed related service in computing Penalty for delays penalty for delays. Further, in case of staggered delivery under Option 2 of Clause 3.12, the payment of penalty for delays in the first part of delivery shall not entitle the Contractor to extend the delivery schedule for the second part and the timeline for the second part shall remain unchanged.
- f) No claim will be made by the Employer for consequential losses due to delay in delivery.

- g) Once the maximum penalty for delays is reached, the Employer may terminate the Contract pursuant to Clause no. 3.52. of the GCC. The maximum amount of penalty for delays shall be **5 % of total Contract Price**. Even in case of the part taking over, maximum ceiling limit remain in reference to **the total contract price**.
- h) The necessary Penalty for delays shall be recovered by the Employer from any stage payment due to the Contractor during any stage payment due to the Contractor.

3.44 INSURANCE OF WORK AT MANUFACTURER'S SITE FOR NEW YARD CRANES:

3.44.1 Unless the Employer shall have approved in writing other arrangements, the Contractor shall, insure, so far as reasonably practicable the Works and keep each part thereof insured as may be mutually agreed between the Employer and the Contractor against all loss or damage from whatever cause arising, until the Yard Cranes are received at destination port, in good condition duly certified by the Third party inspection agency. The value of such shall be at least equal to **100% of the contract price of new Yard Cranes excluding spare parts / tools cost.**

3.44.2 **Insurance during installation at employer's site:** The Contractors shall so far as reasonably practicable insure against the Contractor's liability in respect of any loss or damage occurring whilst the Contractor is at EMPLOYER'S site for the purpose of making good a defect or carrying out the tests on completion during the installation & commissioning of the equipment at employer's site.

3.44.3 The Contractor shall from time to time when so required by the Engineer-In-Charge, produce the policy and receipts for the premium or premiums or satisfactory evidence of insurance cover. All monies received under any such policy shall be applied in or towards the replacement and repair of the Works lost, damaged or destroyed but this provision shall not affect the Contractor's liabilities under the Contract.

3.45 INSURANCE AGAINST THIRD PARTY LIABILITY (FOR NEW YARD CRANES) at Employer site:

3.45.1 Before commencing the execution of work, the Contractor shall insure in the joint names of the IPGL and the Contractor, covering Third Party Liability (TPL) against any damage or loss or injury which may occur to the equipment being installed or to any property or to any person (including property and employees of the Employer) by or arising out of the execution of the Works or temporary Works in carrying out of the Contract. The value of TPL policy shall be Minimum of Euro 29,000 (EuroTwenty nine thousand only) against occurrence of each incidence. The Contractor shall revalidate the insurance coverage after each incidence and keep the insurance coverage till certification of completion.

3.45.2 Such insurance shall be from a reputed Insurance company and should cover all risk and liabilities as

stated in the tender document. The Tenderer shall submit the copy of policy of insurance to Engineer-In-Charge before commissioning of equipment at site and shall be valid till Final Acceptance Certificate.

3.46 COMPENSATION:

The Contractor shall indemnify IPGL in the event being held liable to pay compensation for injury to any Contractor's servants or workmen under the any act of country of destination or any other laws, acts or provisions as applicable and as amended from time to time and shall take out an insurance policy covering all risks under the Act and shall keep the same renewed from time to time as necessary for the duration of the Contract and produce the same before arrival of equipment to the Engineer-In-Charge and shall be valid till issuance of Final Acceptance Certificate (FAC) for the contract.

3.47 DEFAULT OF THE CONTRACTOR:

If the Contractor makes any default or on the happenings of anyone or more of the following events that is to say:

- a) If the Contractor without reasonable cause suspends / abandons the Contract of the Work for a reasonable time after receiving written notice without any lawful excuse or fails to make proper progress with Works after receiving written notice from IPGL or
- b) Fails to give the IPGL proper facilities for inspection of the Works at contractors premises for three days after receiving written notice by IPGL or
- c) The Contractor has become insolvent or
- d) The Contractor has gone into liquidation or passed the resolution for winding up or
- e) Upon the Contractor making an arrangement with or assignment in favour of his creditor or
- f) Upon his assigning this Contract or
- g) Upon an execution being levied upon the Contractor's good or
- h) Upon winding up order being passed by the court or a Receiver or manager is appointed in respect of any of the property of the Contractor or
- i) Possession is taken by or on behalf of any holder of any debentures secured by floating charges of any of the property of the Contractor or
- j) Fails to complete all or any part of the Works during the time specified for completion of the Contract or such extended time as may be granted by the IPGL.

IPGL shall have every right to terminate the Contract after issuing 60 days' notice to the Contractor, on his omission or negligence or neglect or default or failure to comply with any of the condition of the Contract.

3.48 IPGL'S LIEN

IPGL shall have a lien on over all or any money that may become due and payable to the Contractor under this Contract or from any amount lying with [IPGL] in respect of any debt or sum that may

become due and payable by the IPGL to the Contractor under this Contract or other transaction of any nature whatsoever between the IPGL and the Contractor.

3.49 SETTLEMENT OF DISPUTES:

3.49.1 **ENGINEER IN CHARGE'S DECISION:** If disputes of any kind arises between the Employer and the Contractor in any connection with, or arising out of the Contract or the execution of the Works whether during the execution of the Works or after the completion and whether before or after repudiation or termination of the Contract, including any dispute as to any opinion, instruction, determination, certificate or valuation of Engineer, the matter in dispute shall in the first place, be referred in writing to the Engineer In Charge. Such reference shall state that it is made pursuant to this clause. No later than thirty days after the day on which he receives such reference, the Engineer In-Charge shall give notice of his decision to the Contractor. Such decision shall state that it is made pursuant to this clause.

3.49.2 Unless the Contract has already been repudiated or terminated, the Contractor shall, in every case, continue to proceed with the Works with all due diligence and the Contractor and the Employer shall give effect forthwith to every decision of the Engineer-In-Charge unless and until the same shall be revised, as hereinafter provided, in an amicable settlement or an arbitrate award.

3.49.3 If the Contractor is dissatisfied with any decision of the Engineer In Charge or if the Engineer In Charge fails to give notice of his decision on or before the thirtieth day after the day on which he received the reference, then the Contractor may, on or before the seventieth day after the day on which he received the notice of such decision, or on or before the seventieth day after the day on which the said period of 30 days expired, as the case may be, give notice to the Employer, of his intention to commence arbitration, as hereinafter provided as to the matter in dispute. Such notice shall establish the entitlement of the party to commence arbitration, as hereinafter provided, as to such dispute no arbitration in respect thereof may be commenced unless such notice is given.

3.49.4 If the Engineer-In-Charge has given notice of his decision to a matter in dispute to the Employer & the Contractor and no notification of intention to commence arbitration as to such dispute has been given by either the Employer or the Contractor on or before the seventieth day after the day on which the parties received notice as such decision from the Engineer-In-Charge, the said decision become final and binding upon the Employer and Contractor.

3.50 AMICABLE SETTLEMENT:

Where notice of intention to commence arbitration as to the dispute has been given in accordance with Clause 3.49 (Volume-I of Tender Document) arbitration of such dispute shall not be commenced unless an attempt has first been made by the parties to settle such dispute amicably.

Both the Parties shall first make attempt to settle the dispute amicably **and may take assistance of a third party (cost of which will be jointly shared)**. Provided that, unless the parties otherwise, agree, arbitration may be commenced on or after the fifty-sixth day after the day on which notice of

intention to commence arbitration of such dispute was given, whether or not any attempt at amicable settlement thereof has been made.

3.51 ARBITRATION

Disputes if any, between IPGL and the Contractor during the currency of the Contract or after the completion of the work or abandonment thereof shall be settled in accordance with Indian Arbitration & Conciliation Act, 1996 (Amended in 2015) or any statutory modification or re-enactment thereof and rules made there under and for the time being in force shall apply to arbitration proceedings under this Contract. The disputes so raised shall be referred to a panel of two arbitrators, of which one to be appointed by the IPGL and other by the Contractor. The arbitration proceeding shall take place in Mumbai at office of IPGL or at Singapore, as mutually decided by IPGL and the contractor. In case of litigation, the same shall be under jurisdiction of Indian Court/Laws.

3.52 TERMINATION OF CONTRACT:

If the Contractor does not perform the Contractual obligations satisfactorily, as far as Commissioning the equipment for commercial use within stipulated time frame, the Contract is liable to be terminated after issue of notice of 60 (Sixty) days to the Contractor.

3.53 FORCE MAJEURE:

If the supply, Commissioning and Testing of equipment is hindered due to force majeure such as, war, riots, civil commotion, fire, epidemics, natural calamities, etc. such period shall be exempted from completion period as mentioned in clause 3.12 (Volume - I) of this tender document. It is clarified that a change in applicable international laws and regulations, if and to the extent such change results in major change in duties/obligations of the affected party and leads to undesirable impact on contractual obligations, the same would fall within the meaning of "Force Majeure" if it is beyond the control of the affected party and has a material and adverse effect as set out in the contract.

Further, it is clarified that (i) In case the duration of the force majeure is less than **365 days**, the contract will be suspended during this period and after extinction of the force majeure, the contract will continue. (ii) In case the duration of the force majeure is more than 365 days, the contract may be terminated upon mutual consent.

In case of change in applicable international laws and regulations leading to undesired impact in execution of the contract obligation, e.g. prohibiting delivery of equipments at agreed destination port and as per tender terms, then suitable alternative destination and cost implication thereof shall be decided by mutual agreement.

3.54 LABOUR LAWS:

The Contractor shall comply with all the provisions of the destination country or any other local authority Or State regarding Labour Laws and the rules and regulations made there under as amended from time to time and as applicable from time to time with regard to the employees to be deployed by the Contractor for erection, testing, Commissioning of equipment.

3.55 OUTBREAK OF WAR

If during the currency of the Contract, there shall be an outbreak of war (whether war is declared or not) in any part of the world which, whether financially or otherwise, materially affects the execution of the Works the Contractor shall, unless and until the Contract is terminated under the provision in this clause contained, use his best endeavours to complete the execution of the Works, provided always that either the Employer or the Contractor shall be entitled, at any time after such outbreak of war, to terminate this Contract by giving notice in writing to the other, and upon such notice being given this Contract shall terminate, but without prejudice to the rights of either party in respect of any antecedent breach.

3.56 MISTAKE IN CONTRACTOR'S DRAWING

The Contractor shall be responsible for and shall pay for any alterations of the work due to any discrepancies, errors or omissions in the drawings or other particulars supplied by him, whether such drawings or other particulars supplied by him, have been approved by the Engineer In-charge or not.

3.57 DEFAULT OF THE EMPLOYER

In the event of the Employer:

- a) Failing to pay Contractor the amount due under Contract as per stipulated condition or
- b) Interfering with or obstructing the written approval in this Contract, the Contractor shall be entitled without prejudice to any other rights or remedies to terminate his employment under the Contract by giving 90 (Ninety) days prior notice in writing to Employer.

3.58 WARRANTY

During the 24 months or 4000 hrs (whichever is earlier), of the Defects Liability Period the contractor shall post at least one competent, experienced and responsible Technical person who has experience of Erection, Testing and Commissioning of the Equipment, to co-ordinate and execute all works to be attended by the Contractor as per Contractual obligations. The cost for the same shall deemed to be included in the services during guarantee period. The Contractor shall also authorize his technical representative to carry out monthly inspection and submit a monthly report before 10th day of succeeding month to the Engineer-In-Charge. The contractor shall quote for the cost of this service as per price schedule which shall be paid after satisfactory completion of 24 months / 4000 hrs of the Defects Liability Period as certified by the Engineer In charge.

Employer's responsibility during warranty period:

1. To adhere to PMS program supplied by the Contractor with an adequate recording.

2. Exclusive use of original spare parts
3. Replaced parts shall be returned to the Contractor at his cost;
4. To undertake no modification other than by Contractor's authorised personnel;

Warranty shall exclude:

- (i) Operational damages due to mal-operation of crane by IPGL or its authorised representative.
- (ii) Use of improper fuel or auxiliary materials
- (iii) Parts subject to normal wear and tear
- (iv) Damages resultant of wilful and negligent acts (e.g. use of improper tools)

3.59 WARRANTY SUPPORT

The Tenderer shall submit warranty support programme, in detail, covering the methodology and approach which shall be adopted to ensure minimum failures and maximum availability of the cranes. The Tenderer shall provide details of his warranty program and after sales service capability including an organization chart, guaranteed response times to requests for technical assistance and spare parts and a 24-hour help line.

3.60 REFERENCES

The Tenderers shall provide details of similar Yard Cranes that he has recently manufactured together with a list of customers who are willing to act as reference points as per Schedule 18 Reference 1&2.

3.61 Limitation of Liability:

- (i) To the fullest extent permitted by the law, the total liability, in the aggregate, of the Contractor, Contractor's officers, directors, partners, employees, agents, and subcontractors, to Employer (IPGL), and anyone claiming by, through, or under Employer for any claims, losses, costs, or damages whatsoever arising out of, resulting from or in any way related to the Tender from any cause or causes, including but not limited to negligence, professional errors and omissions, strict liability, breach of contract, or breach of warranty, shall not exceed 100% of the Contract Price. Limitation of Liability during defect liability period shall exclude operational damages, due to mal- operation of crane by IPGL or its authorised representative.
- (ii) As regards damages and indemnifications, the Contractor shall not be liable for incidental, indirect or consequential damages to the extent such limitation of liability is valid under Indian law.
- (iii) This clause is enforceable until expiry of entire defect-liability period.

SECTION – 4

4. ENVIRONMENTAL CONDITIONS AT CHABAHAHAR

4.1. GENERAL

The Port is in a sheltered location with natural deep-water close offshore outside the Persian Gulf to the East of the Straits of Hormuz. The surrounding area is characterized by the sea, the atmosphere containing a lot of salt and small particles of sand. The humidity level in the region of the site is high. The region is regarded as one of the most humid of Chabahar Port.

The following is the summary of environmental conditions prevailing at the Site:

- Maximum temperature 50 °C
- Average temperature 25 °C
- Minimum temperature 5 °C
- Average annual rainfall 108 mm
- Maximum annual rainfall 244 mm
- Average humidity 70%
- Maximum humidity 99%
- Climate description sea-climate
- Prevailing wind direction south
- Average wind 99% of the time < 15 m/s
- Maximum gust wind 44 m/s

4.2. TIDES AND STORM SURGE

Tidal Levels with reference to Chart Datum

- Mean of Higher High Water: MHHW +2.53 mCD
- Mean of Lower High Water: MLHW +1.93 mCD
- Mean Sea Level: MSL +1.61 mCD
- Mean of Higher Low Waters MHLW +1.28 mCD
- Mean of Lower Low Waters MLLW +0.69

mCD 3. Quay and yard

- New quay level: +5.00 mCD

The theoretical weight and maximum wheel loads for the crane shall be declared by the tenderer

Storm Surges

Return Period (Year)	Max Storm Surge (m)
2	0.15
10	0.24
25	0.35
50	0.64
100	1.11

4.3. WIND

Direction (Deg)	Speed (m/s) for Return Periods	
	1 in 50 years	1 in 100 years
0	12	13
30	13	13
60	17	18
90	16	17
120	20	22
150	19	20
180	16	17
210	19	20
240	20	21
270	25	27
300	18	19
330	13	14

The maximum gust speed for design shall be taken as 44m/sec.

4.4. WAVES

Based on hydrodynamic and sedimentation studies report, the design wave heights (H_s) and periods (T_p) are as follows :

(a) Waves Generated within Chabahar Bay

Return Period	1 in 10 Years		1 in 25 years		1 in 50 years		1 in 100 years	
	H_s (m)	T_p (Sec)	H_s (m)	T_p (Sec)	H_s (m)	T_p (Sec)	H_s (m)	T_p (Sec)
270	1.4	4.0	1.5	4.1	1.5	4.2	1.6	4.3
300	1.1	3.6	1.2	3.8	1.3	3.8	1.3	3.9
330	1.0	3.5	1.1	3.6	1.2	3.7	1.2	3.8

Source: Consultant's Analysis.

(b) Deep Water Waves

Return Period	1 in 1 year		1 in 10 years		1 in 25 years		1 in 50 years		1 in 100 years	
	H_s (m)	T_p (sec)	H_s (m)	T_p (sec)	H_s (m)	T_p (sec)	H_s (m)	T_p (sec)	H_s (m)	T_p (sec)
120	2.33	6.17	4.1	6.8	4.6	7.3	5.0	7.6	5.3	7.8
150	1.09	5.22	5.1	7.7	6.8	8.5	8.3	9.1	10.5	9.7
180	3.24	7.94	4.6	7.3	5.1	7.7	5.5	8.0	5.8	8.2
210	3.05	7.35	5.0	7.6	5.8	8.2	6.3	8.5	6.8	8.9
240	2.73	7.06	4.1	6.9	4.6	7.3	4.9	7.5	5.2	7.7

Source: Analysis of British Meteorological Office data

(c) *Shallow Water Waves*

Return period	1 in 1 year	1 in 5 years	1 in 10 years	1 in 25 years	1 in 50 years	1 in 100 years
H _s (m)	1.39	2.00	2.25	2.50	2.70	2.90
Direction °N	141	145	145	146	147	148
H _s (m)	0.96	2.70	3.40	4.60	5.10	5.30
Direction °N	156	163	164	166	167	168
H _s (m)	2.69	3.50	3.80	4.20	4.50	4.80
Direction °N	183	182	182	182	182	182
H _s (m)	2.5	3.50	4.00	4.60	4.90	5.20
Direction °N	203	201	200	200	199	199
H _s (m)	2.02	2.70	2.90	3.20	3.40	3.60
Direction °N	223	220	219	218	217	216
H _s (m)	1.25	2.10	2.50	2.80	3.10	3.40
Direction °N	248	242	239	235	233	231

Source : Consultant's analysis

4.5. CURRENTS

Tidal current speed is in the range 0.1 ~ 0.3 m/s.

4.6. RAINFALL

	Rainfall (mm)
Maximum annual rainfall	244.4
Mean annual rainfall	108.2

4.7. TEMPERATURE

Month	Jan	Feb	Mar	Apr.	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Item													
Ave. (°C)	19.20	20.44	23.53	26.57	29.57	31.50	30.80	29.68	27.55	27.43	24.09	21.20	25.98
Ave. Max (°C)	24.32	24.90	27.92	30.81	33.76	34.77	33.52	32.30	30.78	32.32	29.46	26.25	30.04
Ave. Min (°C)	15.10	16.09	19.14	22.32	25.40	27.92	28.08	27.11	24.31	22.56	18.74	16.17	21.91
Abs. Max (°C)	31.00	33.00	38.00	42.00	46.00	47.00	46.00	42.00	42.00	41.00	37.00	32.00	47.00
Abs Min (°C)	7.00	7.00	9.60	14.00	19.20	22.00	21.00	23.00	19.00	13.20	9.20	7.00	7.00

The maximum ambient temperature for design shall be taken as 50°C

The Minimum ambient temperature for design shall be taken as 5° C.

4.8. HUMIDITY (As a percentage)


Months													
Time of Reading	Jan	Feb	Mar	Apr.	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Year
06:30	68.96	72.13	76.46	79.29	81.96	84.3	82.83	83.17	79.42	81.92	77.48	74.78	78.46
12:30	52.92	56.21	58	60.88	64.13	67.8	70.71	70.46	63.46	60.42	55.3	52.13	61.07

The maximum relative humidity for design shall be taken as 99%

5.18 DRAWINGS.

The drawing of jetty layout is attached as **Annexure-I**.

ANNEX -I
LAYOUT MAP OF CHABAHAR PORT



ANNEX - II
BANK GUARANTEE FORMAT FOR EMD

KNOW ALL BY THESE PRESENTS THAT ----- (Name of the Bank), a Banking corporation carrying on banking business including Guarantees at Mumbai and other places and having its office at ----- Mumbai (hereinafter called 'The Bank' which expression shall unless excluded by or repugnant to the context or meaning thereof be deemed to include its successors and assigns) SEND GREETINGS:

WHEREAS The Board of Directors, of INDIA PORTS GLOBAL LTD constituted under the COMPANY Act, 2013 (hereinafter called 'The Board' which expression shall unless repugnant to the context or meaning thereof be deemed to include its successors and assigns) had invited tenders for Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of All –Terrain 100 Ton. Capacity and 3 Nos. of Rough-Terrain 60 Ton. Capacity Yard Cranes at IPGL site.

(hereinafter called Tender) as per Instruction to the Tenderers, General conditions of the Contract, scope of work, specifications, clarifications/amendments/corrigendum/addendums and Price schedule covered under 'Tender No. –IPGL/Yard Cranes/2018.

AND WHEREAS M/s ----- (hereinafter called the 'Tenderer') has offered to carry out the work under the said Tender.

AND WHEREAS under the conditions of the Contract, the Tenderer is required to give a Earnest Money Deposit in the form of Bank Guarantee from a Scheduled Bank/Nationalised Bank having its branch in Mumbai for the sum of Rs. ----- (Rupees -----) / Euros _____ (Euros _____)

AND WHEREAS M/s ----- have requested the Bank to furnish a Guarantee to the Board for the sum of Rs. ----- (Rupees -----) / Euros _____ (Euros _____) which the Bank has agreed to do in the manner hereinafter appearing.

NOW THIS INDENTURE WITNESSETH that the said Bank doth hereby stand surety for the said sum of Rs. _____ (Rupees -----) / Euros _____ (Euros _____)

AND DOTH HEREBY GUARANTEE TO AND COVENANT WITH AND irrevocably agree to pay to the Board upon demand in writing without referring to M/s ----- (Name of the Tenderer) and without questioning the right of the Board to make such demand or the propriety or legality of such demand, such sum or sums not exceeding in the whole a sum of Rs. ----- (Rupees -----)/ Euros _____ (Euros _____) as may be payable to the Board by the Tenderer by reason of withdrawing his Tender before the expiry of the day from the last date of the submission of the Tender or such time as may be extended by the Board to which M/s ----- have agreed in writing, or in the event of the tender being accepted by the Board and fails to enter into a Contract or to furnish Performance Guarantee as per

the terms of the Contract, in respect of which the decision of the Board shall be final and legally binding and the said Bank doth further covenant and declare that this security is irrevocable and shall remain in force up to and inclusive of the ----- (date) and if the Contract is not awarded by the Board before the expiry of the aforesaid date, the said Banker undertakes to renew this Guarantee from month to month until 6 months after the aforesaid date i.e. up to ----- (date) and the said Bank doth hereby further covenant and declare that if the said M/s -- -----(tenderer) do not obtain and furnish renewals of this Guarantee for a further period of six months to the

Board not less than 30 days prior to the expiry of the period of this Bank Guarantee or renewals thereof as to keep the same valid and subsisting till the Contract is awarded by the Board and for 6 months thereafter i.e. up to ----- the entire amount of this Bank Guarantee in default of obtaining and furnishing the renewals of this Bank Guarantee in the manner and within the time aforesaid shall become forthwith due and payable to the Board notwithstanding :

1. that the period of the Guarantee of the renewal or renewals thereof has not expired or,
2. that the period of Guarantee of the renewal or renewals thereof has already expired

AND THE BANK further declares that notwithstanding anything to the contrary contained hereinabove, the Bank's liabilities under the Guarantee is restricted to Rs. ----- (Rs. -----) / Euros ----- (Euros -----) and unless a demand in writing under the Guarantee is made with the Bank within the 3 months from the date of expiry i.e. by -----, all the rights of Board under this Guarantee shall be forfeited and the Bank shall be relieved and discharged from all liability there under:

Notwithstanding anything to the contrary contained herein:

Our liability under this Bank Guarantee shall not exceed Rs. ----- (Rupees -----) / Euros ----- (Euros -----)

This Bank Guarantee shall be valid up to -----; and

We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only and only if you serve upon us a written claim or demand on or before ----

IN WITNESS WHEREOF, the duly constituted attorneys of the Bank has here up to set his/their hands and seals on the ----- of -----2018.

SIGNED, SEALED AND DELIVERED

By the within named -----

Through it's duly -----

Constituted Attorney Mr. -----

& ----- in the presence of

LETTER OF APPLICATION CUM TENDER FORM

To be submitted on company Letter Head by the Tenderer indicating full postal address, telephone number/s, fax number/s, email id, etc.

To,

Date:

India Ports Global Ltd

4th Floor, Nirman Bhavan,

M.P. Road, Mazgaon,

Mumbai-400010 – INDIA.

Sub: Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes at Shahid Beheshti Port, Chabahar.

REF: Tender No:**IPGL/Yard Cranes/2018**

Sir,

Being duly authorised and represent and act on behalf of M/s._____ hereinafter called the 'Tenderer' and having fully understood Instructions to Tenderer/s, General Conditions of Contract, Scope of Work, Drawings & Specifications, clarifications/amendments/corrigendum/addendums and Price schedule as given in the Tender Document and after visiting the Site, the undersigned hereby submits the Offer for the subject Works.

2. IPGL and its representatives are hereby authorised to conduct any enquiry or investigations to verify the statements, documents & information submitted in connection with this Tender and to seek clarifications from our bankers & Clients regarding any financial, commercial & technical aspects. This letter of application will also serve as authorization to any individual or representatives of any institution referred to in the supporting information, to provide such information deemed necessary and requested by yourself to verify statements and information provided in this Tender, or with regard to the resources, experience, and competence of the Tenderer.

3. Tenderer's representatives may contact following IPGL persons for further information:

For General & Managerial inquiries	
Name of Contact Person	Mr Arun Kumar Gupta
Telephone number/s	022 69000430, 9833880764
Fax number/s	022 66566336
E-mail Id	md.indiaportsglobal@gmail.com

For Technical inquiries	
Name of Contact Person	Mr Ashok Gadkari
Telephone number/s	022 69000432, 9004762185
Fax number/s	022 66566336
E-mail Id	mt.indiaportsglobal@gmail.com,

For Financial inquiries	
Name of Contact Person	Mr Nitin Shah
Telephone number/s	022 69000433, 9769036703
Fax number/s	022 66566336
E-mail Id	cs.indiaportsglobal@gmail.com,

4. This application is made in the full understanding that:

- i. Tenders received from Tenderers will be subject to verification of all submitted information.
- ii We agree to abide by this Tender for the period of 180 days from the last date fixed for receiving the same and it shall remain binding upon us and may be extended at any time, if requested by IPGL, before the expiry of the validity period as given in this Tender.
- iii Notwithstanding anything contained in this tender document, IPGL reserves the right to annul the bidding process at any time without any liability or any obligation for such annulment, without assigning any reason.

- iv. If our Tender is accepted, we confirm to commence work from the date of issue of `Letter of Acceptance'(LOA) and to complete all Works in good condition within the completion period as stipulated in this Tender.
- v. If our Tender is accepted, we will furnish the Security Deposit and Performance Guarantee Bond for the due Performance of the Contract. The amount and format of such Guarantee will be in accordance with the subject Tender and Conditions of Contract.
- vi. We have independently considered the amount/rate shown as penalty for delay in completion of Works and agree that the same represent a fair estimate of the damages/losses likely to be suffered by IPGL in the event of delay in overall completion of the Work.
- vii. We have downloaded the tender form from web site and we hereby certify that we have not made any changes to the Tender Document either in words or in sentences or deleted or added any word or sentences from/to the tender document.

5. The undersigned declares that the statements made & the information provided in the duly filled Forms are complete, true & correct in every detail.

6. Witness

Signature
Name and Designation with company seal
For & on behalf of (name of the Tenderer)

Signature
Name and Designation with company seal

Witness

Signature
Name and Designation with company seal
For & on behalf of (name of the Tenderer)

Signature
Name and Designation with company seal

ANNEX - IV

FORM OF AGREEMENT

THIS AGREEMENT made at Mumbai this _____ day of _____ BETWEEN _____ (hereinafter called "the Contractor") which expression shall unless excluded by or repugnant to the context or meaning thereof be deemed to include the party named and his heirs, executors and administrators or its successors and permitted assigns) of the one part and INDIA PORTS GLOBAL LIMITED, Mumbai incorporated by Companies Act 2013 being the successors (herein after called "The Employer") which expression shall unless excluded by or repugnant to the context or meaning hereof, be deemed to include their successors and assigns) of other part

WHEREAS the Board have accepted a tender by the Contractor for Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes at Shahid Beheshti Port, Chabahar.

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

1. In this agreement words and expressions shall have the same meaning as are respectively assigned to them in the conditions of Contract hereinafter referred to.
2. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz -
 - a) The said tender
 - b) The acceptance of tender(LOA)
 - c) The conditions of Contract
 - d) The specification, drawings/annexures
 - e) The Price, schedule and all other schedules
 - f) The Contractor's specification and all correspondence, by which the Contract is added, amended, varied or modified in any way by mutual consent.
3. In consideration of the payments to be made to the Contractor as hereinafter mentioned the Contractor HEREBY CONVENANT with the Employer to Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes in conformity in all respects with the provision of the Contract.
4. The Employer HEREBY CONVENANT to pay to the Contractor in consideration of the Design, Manufacture, Supply, Installation, Testing, Commissioning and handing over the 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes, as per the Contract Price at the time and in the manner prescribed by the Contract.

5. IN WITNESS WHEREOF the Contractor that hereunto set his hand and seal and the Managing Director, India Ports Global Limited for and on behalf of the Board has set his hand and seal and the common seal of the Employer has been hereunto affixed the day and year first above written.

Signed, sealed and delivered

by _____ for and on behalf of the said

_____ in pursuance of a resolution of

the Board of Directors of the

passed at a meeting held on

Managing Director

the _____ CONSTITUTED ATTORNEY

_____ or

The Common Seal of the Contractor was hereto affixed in the presence of

SIGNED, SEALED AND DELIVERED

by The Managing Director,

for and on behalf of the Board of Directors of

India Ports Global Private Limited

with the Common Seal of the Board

of Directors

ANNEX -V

FORMAT OF BANK GUARANTEE to be used FOR (i) PERFORMANCE of the Contract (ii) Performance of equipment during defect liability period and (iii) after completion of defect liability period for the contract.

In consideration of the India Ports Global Limited incorporated under Companies Act, 2013 (hereinafter called “The Employer” which expression shall unless excluded by or repugnant to the context or meaning thereof be deemed to include the Board of Directors of India Ports Global Private Limited, its successors and assigns) has awarded the Contract for “Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes”, vide Managing

Director, IPGL’s letter No. -----, dated ----- (hereinafter called ‘the said Contract’) to ----- (Name of the Contractor) (hereinafter called the ‘Contractor’). Under the terms and conditions of the Contract, made between the Contractors and the Employer, the Contractor is bound to submit a performance Guarantee of Euros ----- (In words Euros ----- only) / Rs. ----- (in words Indian Rupees -----) to Employer, we the ----- (Name of the Bank and address) (hereinafter referred to as ‘the Bank’) at the request of the Contractors do hereby undertake to pay to the Employer an amount not exceeding Euros ----- (Euros ----- only) / Rs. ----- (in words Indian Rupees -----) against any loss or damage caused to or suffered or which would be caused to or suffered by the Employer by reason of any breach by the Contractors of any of the terms and conditions of the said Contract.

1. We -----Bank do hereby undertake to pay the amounts due and payable under this guarantee without any demur merely on a demand from the Employer stating that the amount claimed is due by way of loss or damage caused to or which would be caused to or suffered by the Employer by reason of the Contractor’s failure to perform the said Contract. Any such demand made on the Bank shall be conclusive as regards the amount due and payable by the Bank under this Guarantee. However, our liability under this Guarantee shall be restricted to an amount not exceeding Euros----- (Euros ----- only) / Rs. ----- (in words Indian Rupees -----)
2. We, ----- (Name of the Bank) undertake to pay to the Employer any money so demanded notwithstanding any dispute or disputes raised by the Contractor in any suit or proceeding before any court of Tribunal relating thereto our liability under this present being absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and the Contractor shall have no claim against us for making such payment.
3. We, ----- further agree with the Employer that the guarantee herein contained shall remain in full force and effect during the period that would be taken for the performance of the said Contract and it shall continue to be enforceable till all the dues of the Employer under or by virtue of the said Contract have been fully paid and its claims satisfied or discharged or till the Managing Director of the said Employer certified that the terms and conditions of the said Contract have been fully and properly carried out by the said Contractors and accordingly discharge this guarantee. Unless the demand or claim under this guarantee is made on us in writing on or before the -----, we shall be discharged from all liabilities under this guarantee thereafter. This Guarantee will remain in force from the date hereof, i.e. till ----- and unless a demand or suit or action to enforce any claim under the guarantee is made within three months from the date

of expiry of this guarantee, i.e. on or before ----- all your rights under this guarantee shall be forfeited and we shall be relieved and discharged from all liabilities under this guarantee.

4. We, ----- Bank further agree with the Employer that the Employer shall have the fullest liberty without our consent and without affecting in any manner our obligations hereunder to vary any of the terms and conditions of the said Contract or to extend the time of performance by the said Contractors from time to time to postpone from any time or from time to time any of the powers exercisable by the Employer against the said Contractors and to forebear or enforce any of the terms and conditions relating to the said Contract and we shall not be relieved from our liability by reason of any such variation or extension being granted to the Contractors or for any forbearance, act or omission on the part of the Employer or any indulgence shown by the Employer on the part of the Employer or any indulgence shown by the Employer on the part of the Employer or any indulgence shown by the Employer to the Contractors or by any such matter or thing whatsoever which under the law relating to sureties would but for this provision, have effect of so relieving us.
5. This Guarantee will remain valid for the entire period as agreed, even though there happens to be change in the constitution of the bank or that of the Contractor.

It is also hereby agreed that the applicable Court in India shall have exclusive jurisdiction in respect of claims, if any, under this Guarantee.

We, ----- Bank lastly undertake not to revoke this guarantee during its currency except with the previous consent of the Employer in writing.

Dated ----- day of -----2018.

For (Name of the Bank)

Signature

Seal of The Bank

(Name with Designation)

ANNEX -VI

FORM OF BANK GUARANTEE (SECURITY DEPOSIT)

(For Advance Payment)

- 1 In consideration of the India Ports Global Private Limited incorporated under Companies Act, 2013 (hereinafter called “The Employer” which expression shall unless excluded by or repugnant to the context or meaning thereof be deemed to include the Board of Directors of India Ports Global Private Limited, its successors and assigns) has awarded the Contract for Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT) Yard Cranes vide Board’s Managing Director’s letter No. -----, dated ----- (hereinafter called ‘the said Contract’) to ----- (Name of the Contractor) (herein after called the ‘Contractor’). Under the terms and conditions of the Contract, made between the Contractors and the Employer, the Contractor is bound to submit a Bank Guarantee towards security deposit, (against advance payment as per terms of contract) for Euros ----- (Euros ----- only) / Rs -----(Rupees-----) to Employer, we the ----- (Name of the Bank and address) (hereinafter referred to as ‘the Bank’ at the request of the Contractors do hereby undertake to pay to the Employer an amount not exceeding Euros ----- (Euros ----- only) / Rs -----(Rupees-----)against any loss or damage caused to or suffered or which would be caused to or suffered by the Employer by reason of any breach by the Contractors of any of the terms and conditions of the said Contract.
- 2 We ----- Bank do hereby undertake to pay the amounts due and payable under this guarantee without any demur merely on a demand from the Employer stating that the amount claimed is due by way of loss or damage caused to or which would be caused to or suffered by the Employer by reason of the Contractor’s failure to perform the said Contract. Any such demand made on the Bank shall be conclusive as regards the amount due and payable by the Bank under this Guarantee. However, our liability under this Guarantee shall be restricted to an amount not exceeding Euros ----- (Euros ----- only) / Rs -----(Rupees-----)We, ----- (Name of the Bank) undertake to pay to the Employer any money so demanded notwithstanding any dispute or disputes raised by the Contractor in any suit or proceeding before any court of Tribunal relating thereto our liability under this present being absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and the Contractor shall have no claim against us for making such payment.
- 3 We, ----- further agree with the Employer that the guarantee herein contained shall remain in full force and effect during the period that would be taken for the performance of the said Contract and it shall continue to be enforceable till all the dues of the Employer under or by virtue of the said Contract have been fully paid and its claims satisfied or discharged or till the Managing Director of the said Employer certified that the terms and conditions of the said Contract have been fully and properly carried out by the said Contractors and accordingly discharge this guarantee. Unless the demand or claim under this guarantee is made on us in writing on or before the -----, we shall be discharged from all liabilities under this guarantee thereafter. This Guarantee will remain in force from the date hereof, i.e. till ----- and unless a

demand or suit or action to enforce any claim under the guarantee is made within three months from the date of expiry of this guarantee, i.e. on or before ----- all your rights under this guarantee shall be forfeited and we shall be relieved and discharged from all liabilities under this guarantee.

- 4 We, ----- Bank further agree with the Employer that the Employer shall have the fullest liberty without our consent and without affecting in any manner our obligations hereunder to vary any of the terms and conditions of the said Contract or to extend the time of performance by the said Contractors from time to time to postpone from any time or from time to time any of the powers exercisable by the Employer against the said Contractors and to forebear or enforce any of the terms and conditions relating to the said Contract and we shall not be relieved from our liability by reason of any such variation or extension being granted to the Contractors or for any forbearance, act or omission on the part of the Employer or any indulgence shown by the Employer on the part of the Employer or any indulgence shown by the Employer on the part of the Employer or any indulgence shown by the Employer to the Contractors or by any such matter or thing whatsoever which under the law relating to sureties would but for this provision, have effect of so relieving us.
- 5 This Guarantee will remain valid for the entire period as agreed, even though there happens to be change in the constitution of the bank or that of the Contractor.

It is also hereby agreed that the applicable Court in India shall have exclusive jurisdiction in respect of claims, if any, under this Guarantee.

We, ----- Bank lastly undertake not to revoke this guarantee during its currency except with the previous consent of the Employer in writing.

Dated ----- day of -----2018.

For (Name of the Bank) (Name with Designation)

Signature/ Seal of the Bank

ANNEX –VII

SCOPE OF WORK FOR THIRD PARTY INSPECTION AGENCY (TPIA) TO BE APPOINTED BY IPGL

1. Approval of Main Structure Analysis Results
 - a. Check for Design Criteria
 - b. Check for Stress Results
 - c. Check for Fatigue Stress
 - d. Check for Main Structure Drawings of: Girder, Boom, Girder Support Beam, Leg, Portal Beam, Sill Beam, Top Leg, Top Beam, Fore-Stay & Back-Stay, Leg Diagonal, Top Leg Brace, Boom Hinge, Boom Stop Girder.
 - e. Check the results and conformity with the technical specification of performance test.
2. Documents Review:
 - a. Technical Specification
 - b. Approved Construction drawings
 - c. Inspection and Test Plan
 - d. WPS/PQR-WPQR
 - e. NDE Procedures & NDE Personnel Certificates
 - f. DE Procedures & DE Personnel Certificates
 - g. Painting Procedure
 - h. Commissioning Procedure etc.
 - i. Review of raw material test certificate for compliance with code/specifications and identification of material with manufacturer's test certificate.
 - j. Review of heat treatment records carried out where applicable.
 - k. Examination of radiographs including review of radiographic technique and monitoring of other NDT requirements such as Ultrasonic, Magnetic particle and Liquid Penetrant testing are met with as per the relevant code/drawings/ QAP.
 - l. Review of test certificate for all critical items but no limited to for:
 - Bogies, Portal, Main girder and boom girder beam, Trolley & Loading devices
 - Long travel, Trolley traversing, Main Hoist, Boom Hoist
 - Motors, Controller, Main Cables, Other bought out components any other like anemometer, rail clamps, hold down devices, rail sweeper, all safety devices, wire ropes etc.
3. Material Verification:
 - a. Review Mill Certificate
 - b. Verify the material traceability records

c. Witness material test as per submitted QAP

4. Witness & Verification

a. Witness Welder Qualification Test and certification by TPI

b. Fit-up: witness on critical parts and randomly spot witness for the others

c. Welding Process: monitoring/patrol inspection

d. Non Destructive Test: review NDT results, spot check on the calibration of equipment & verify the qualification of personnel

e. Final Inspection: witness on the final welds and dimensional/straightness

f. Sub-assembly: witness on the final welds, alignment, dimension.

g. Erection: witness on the final welds, final dimensional, bolt torque, levelling/straightness.

h. Painting: witness on the surface preparation (after sand blasting), painting procedure and randomly spot check on the final DFT.

i. Testing:-

i) Electrical: review continuity check & megger test; verify electrical equipment installation etc.

ii) Mechanical: witness alignment/installation, bolt torque, greasing/lubricating, idle running test, etc.

j. Commissioning: witness on all testing as per approved commissioning procedures, including load test.

k. Witness assembly of all the primary structural with the machinery and electrical equipment, spreader and safety devices at site.

l.

5. Documentation & Certification

a. Submit FORTNIGHTLY inspection report to IPGL

b. Certification of parts of the crane before shipment to berth as per tender.

c. Certification of completion of installation & erection activities as per tender.

d. Certification of the crane for meeting the FEM classification and requirements as per TPIA.

e. Certification of the crane for “Ready to ship” prior to shipment from contractor’s site indicating that all the tests are successfully carried out as detailed in the tender document as per clause 27 (Vol-II).

f. Certification of completion of commissioning & testing as per contract.

g. Stamping and issue of certificates.

SCHEDULE 1

GENERAL INFORMATION

Page1/2: Schedule -1

All individual firms submitting the tender must complete the information in this form.

1.	Full name of the Firm:	
2.	Head Office address:	
3.	Contact person name at Head office:	
4.	Telephone number/s:	
5.	Fax number/s:	
6	E-mail Id	
7.	Branch Office address, if any:	
8.	Contact person name at Branch office:	
9.	Telephone number/s:	
10.	Fax number/s:	
11.	E-mail Id	
12.	Works address:	
13.	Contact person name at Works:	

Page 2/2: Schedule -1

14.	Telephone number/s:	
15.	Fax number/s:	
16.	E-mail Id	
17.	Place of Registration/Incorporation:	
18.	Year of Registration/ Incorporation	
19.	Details of Mainlines of Business:	
	<hr/>	
	<hr/>	
	<hr/>	
	i.	Since
	ii.	Since
	iii.	Since
	iv.	Since
	v.	Since

Signature & seal of the Tenderer

SCHEDULE 2

FINANCIAL DATA

Page: 1/1 Schedule 2

Tenderers should provide financial information as detailed below to demonstrate that they meet the Qualifying requirements for shortlisting. Each Tenderer must fill the information in this format only. If required, you may use separate sheets to provide complete financial information.

In support of submitted information, copies of Audited 'Balance Sheets' and 'Profit & Loss account' statements for last three (03) years must be attached.

A: Summaries of turnover and profit/loss for the last 03 years

Financial information in	Previous three years		
	2014-2015 or 2015	2015-2016 or 2016	2016-2017 or 2017
Turnover			
Profit before tax			
Profit after tax			

B: Income tax and Sales tax details (For domestic suppliers):

1. Permanent Income-Tax Account Number (PAN)	
2. Sales tax registration number	

(Kindly enclose copies of supporting documents for above information)

Signature & Seal of the Tenderer

SCHEDULE 3

WORK SCHEDULE

Supply of 3 Nos. of 100 Ton capacity All-Terrain (AT) and 3 Nos. of 60 Ton capacity Rough-Terrain (RT)

Yard Cranes.

- 3.1 Work schedule for design and manufacturing of the cranes at work. (A bar chart/CPM/pert for the entire completion period)
- 3.2 Shipment Schedule.
- 3.3 Unloading Schedule.
- 3.4 The time required for mobilizing the equipment at Chabahar Port including details of transportation, Installation, Commissioning & Testing of equipment
- 3.5 Manpower deployment during Installation, Testing and commissioning phase
- 3.6 Tenderer can indicate the minimum length of berth and period that will be required for Installation, Commissioning & Testing of the new Yard Cranes at site, Chabahar Port.
- 3.7 Requirement for office space and other facilities, if any, to be provided by the IPGL/ Chabahar Port during Installation, Testing and Commissioning period.

Signature & Seal of the Tenderer

SCHEDULE 4
TRAINING SCHEME

The Tenderer shall describe in detail the training scheme that he is proposing for technicians, operators and supervisory personals of the Employer for efficient functioning of the equipment to be supplied by him. The scheme shall indicate the nature and duration of training required for various categories of personnel. The following particulars shall be furnished in the format given below: -

Sr. no.	Designation of each Trainer personnel of supplier and area of Training assignment.	Recommended no. of person to be trained in each category	Duration of training for each category

Signature & Seal of the Tenderer

SCHEDULE 4-A

1. TRAINING OF CRANE OPERATORS & MAINTENANCE PERSONNEL:

GENERAL:

The contractor can assign qualified mechanical/hydraulic and electrical / electronic specialists to instruct the employers Terminal operations personnel in the Eco-Driving / Operating and cost effective maintenance on all equipments installed under this contract. The training session by OEM for Hydraulics, Electrical & Electronic Components / Mechanisms will be performed at the site of the work. The contractor shall submit his fully structured and detailed proposed training programme under this contract.

TRAINING SESSIONS:

1 The training sessions shall include operations, maintenance and servicing of all mechanical/hydraulic and electrical / electronic components of the Yard Cranes. The detailed training programme will be finalized by the Contractor in consultation with the employer well in advance. The training shall be in sufficient depth to enable IPGL to use and maintain the Yard Cranes in a safe and proper manner. Contractor shall impart operational & maintenance training to employer's personnel as per the following;

Location	Details	Total Training Days
At employer's site cost to be quoted in price schedule.	A)Mechanical / Hydraulic System Control system & Maintenance / Trouble Shooting /Repairs B)Electrical /Electronic Control System & Maintenance / Troubleshooting / Repairs	5 days

In class room at IPGL site.	Electrical / Electronic Control Systems & Maintenance / Trouble Shooting / Repairs	5
	Yard Cranes Operations / Mechanical / Hydraulic System Electrical / Electronic Control Systems	5
On Yard Crane at IPGL site.	Mechanical / Hydraulic System	5
	Electrical / Electronic Control Systems & Maintenance / Trouble Shooting / Repairs	5
	Yard Cranes Operations: i) Economical Driving & Lifting Techniques. ii) Improving Knowledge of RPM v/s Torque. iii) Interpreting Information Provided on the Display. iv) How the Driver can affect Fuel Consumption & Emissions.	5

2 The session shall also include hand-on-trouble shooting where the contractor inserts known faults into the system to demonstrate the fault diagnostic capabilities of the fault diagnostic.

3 The contractor shall furnish detailed Training manual to employer 15 days before commencement of training.

4 The contractor shall provide a full time engineer on the contractor's permanent payroll, on site who shall oversee the Erection / commissioning works. He shall have authorization to make reasonable changes and modifications as required by the employer.

5 A commissioning engineer with knowledge of Electrical & Electronic Components / Mechanisms shall remain at site for the first two weeks of the performance test period of each equipment.

SCHEDULE 5

QUALITY ASSURANCE PLAN (QAP)

All stages of execution of the work shall be governed by Quality Assurance Procedures that shall comply with or better requirements of ISO standards. Tenderer shall submit in substantial detail a quality assurance plan indicating all activities step by step at various manufacturing/fabrication/construction premises including site to carry out to meet the requirement of this specification and International standards/regulations/practices to enable comprehensive assessment of its merit and reliability. This shall also indicate tentatively at what stages of manufacturing/ fabrication/construction of all items he proposes the customer control points according to which the inspection by the Employer and Engineer-In Charge could be planned.

The bidder must provide QAP for all items except for those which are bought out items from various suppliers.

QAP of the same may be provided at an appropriate stage.

QAP shall incorporate monitoring, inspection, Testing and Review as per the scope of Third Party Inspection Agency (TPIA) to be appointed by the supplier, as given in the Annex VII of tender document.

Signature & Seal of the Tenderer

SCHEDULE 6

DETAILS OF INSTRUMENTS

FOR TESTING & QUALITY CONTROL

Tenderers are advised to furnish details regarding instruments that he will be using for 'Testing & Quality Control' till completion of the subject Work. The information in this regard should be submitted in below mentioned format and separate sheets may be used to furnish necessary details, if required.

Sl. No.	Brief Description & specifications of Testing & Quality Control Instruments	Qty	Year of Installation
1.			
2.			
3.			
4.			
5.			
6.			
7.			
8.			
9.			
10.			

Signature & Seal of the Tenderer

SCHEDULE 7

SUB-CONTRACTORS

The Tenderer shall submit the name, address of persons, firms or companies, proposed by him as sub Contractors for carrying out the work under the Contract together with particulars of work to be carried out by each party. Written confirmation from sub Contractor shall be submitted along with the tender.

Sl. No.	Section of Works	Name and address of the proposed Supplier/sub-contractor	Name & Location of the Organisation previously supplied/worked
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			

Signature & Seal of the Tenderer

SCHEDULE 8

ARRANGEMENT FOR SPARE PARTS

Tenderer shall submit following information pertaining to availability of spare parts

1	Name, address and Contact Number of Service Centres of tenderers firm with spare parts stock in India/Shahid Behesti Port.	
2	The address of the dedicated website through which order for spare parts can be placed.	
3	Minimum number of days, on intimation, a service Engineers of tenderer's firm for this particular Equipment is available on site.	

Signature & Seal of the Tenderer

SCHEDULE 9

STATEMENT OF DEVIATIONS

1. The following are the particulars for deviations from the requirements of the Tender specifications (Technical):

Clause Ref.	Proposed Deviations	Justification for proposed deviation.

2. The following are the particulars for deviations from the requirements to the instructions to Tenderers and Conditions of Contract:

Clause Ref.	Proposed Deviations	Justification for proposed deviation.

- Note- 1.** Where there are no deviations, the statement should be returned in duly signed manner with an endorsement indicating “ No Deviations “.
2. The Tenderer may indicate the Price adjustment in terms of percentage against each deviation, which he may like to add to the Tender Price for withdrawing his deviation, if the same is unacceptable to the Employer. The price adjustment for such deviation shall be given in the respective price-bid only and not anywhere in the tender.
3. In case of no submission of price-adjustment against any deviation, it will be deemed acceptance by the contractor without any price adjustment.

Signature and seal of the Tenderer

Schedule -10

LIST OF SPARE PARTS/ Tools to be supplied under this contract.

Consolidated List for 3 units of 100 Ton (AT) and same for 3 units of 60 Ton. (RT) capacity Yard Cranes to be submitted separately.

Supply of Spare parts shall be separate from scope of this tender, being optional on the part of IPGL and not taken for evaluation of the bids.

I. SPARES:

Details	Spares	Qty
---------	--------	-----

To be filled in by tenderer as per Clause No. 18, 19 & 20 of Vol. II, for 100 Ton and Clause No. 32 A, B & C of Vol. II for 60 Ton capacity Yard Cranes.

SCHEDULE 10 A

OPERATIONS AND MAINTENANCE MANUALS

1 OPERATING AND MAINTENANCE (O&M) MANUAL

- 1.1 The contractor shall provide an operating and maintenance (O&M) manual which will cover the operation, lubrication, maintenance and inspection of the crane including routine and major maintenance of mechanical, hydraulics and electrical/electronic components. Routine and major inspection of the structure shall be covered by the structural maintenance manual. Detailed electrical record drawing/circuit diagrams shall be included with each O&M manual.
- 1.2 The O&M manual shall be durable and hardbound with properly indexed for easy reading. The contractor shall furnish 4 sets of O&M manuals with the supply of each cranes. The contractor shall also provide O&M manual on a CD for reference. These manual shall be supplied 15 days before commencement of training schedule and commissioning of the equipment at employer's site. The O & M manuals shall consist following;
- .1 A fully detailed as constructed manufacturing specification of the crane and equipment including, without limitation:
- Drawings and diagrams where appropriate including electrical diagrams and hydraulic schematics.
 - All materials and component parts test certificates
 - A schedule of third party supplied components.
 - A schedule of spare parts/spare parts catalogue for indenting spares provided under the contract.
- .2 A fully detailed as constructed performance specification of the crane and equipment including, without limitation:
- Wheel loading
 - Operating speeds and limitations
 - Commissioning test results including current readings
 - Statutory test certificates
- .3 A fully detailed operating and maintenance manual for the crane, equipment and component parts including without limitation:
- Setting up and testing procedures
 - Operational duties and restrictions
 - Maintenance and replacement schedules.

Schedule 11. i.e. Format of PRICE SCHEDULE-Part I A
(Tender No. IPGL/YARD CRANES/2018)

Name of Work: Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 100 Ton (AT) capacity Yard Cranes at Shahid Beheshti Port, Chabahar.

S r . N o	Description (Part I) A	Price Quoted for new Yard Cranes (In EURO/INR)		
		Currency	In Figures	In words
1.	Equipment			
	CIF price for Design, Manufacture, Transportation and Supply of 3 units of 100 Ton cap. All Terrain Yard Cranes to IPGL, Shahid Behesti Port, Chabahar including Transit / Marine Insurance including Other taxes, duties, levies if any, payable at country of origin/country of export.			
2.	Service component			
	A) Price for Training fee for imparting operational & maintenance training, as per the Tender document and as per training schedule provided as per schedule 4 and 4 A.			
	B) Price for providing 06 sets of operation and Maintenance manuals and “As-built” drawings and spare parts catalogue as per tender conditions.			
	C) Price for providing 04 sets of Training manuals.			
3.	Price for rendering warranty support as per tender conditions.			
	TOTAL OF 1 TO 3: TOTAL Landed Cost of 3 units of 100 Ton (AT) capacity (PRICE SCHEDULE-11 PART-1 A)			

Note: Tenderer shall submit their offer for the entire work. Partial offer and conditional offer by any tenderer shall be liable for rejection.

Price schedule Part 1A, 1B and part II shall be submitted in separate sealed envelopes and shall be kept in Envelope IV.

Name, Designation and Signature of
Tenderer with company seal & date.

Name

Signature of witness

**Schedule 11. i.e. Format of PRICE SCHEDULE-Part I B
(Tender No. IPGL/YARD CRANES/2017)**

Name of Work: Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos. of 60 Ton (RT) capacity Yard Cranes at Shahid Beheshti Port, Chabahar.

S r . N o	Description (Part I) B	Price Quoted for new Yard Cranes (In EURO/INR)		
		Currency	In Figures	In words
1.	Equipment			
	CIF price for Design, Manufacture, Transportation and Supply of 3 units of 60 Ton cap. Rough Terrain Yard Cranes to IPGL, Shahid Behesti Port, Chabahar including Transit / Marine Insurance including Other taxes, duties, levies if any, payable at country of origin/country of export.			
2.	Service component			
	A) Price for Training fee for imparting operational & maintenance training, as per the Tender document and as per training schedule provided as per schedule 4 and 4 A.			
	B) Price for providing 06 sets of operation and Maintenance manuals and “As-built” drawings and spare parts catalogue as per tender conditions.			
	C) Price for providing 04 sets of Training manuals.			
3.	Price for rendering warranty support as per tender conditions.			
	TOTAL OF 1 TO 3 : TOTAL Landed Cost of 3 units of 60 Ton (RT) capacity (PRICE SCHEDULE-11 PART-1 B)			

Note: Tenderer shall submit their offer for the entire work. Partial offer and conditional offer by any tenderer shall be liable for rejection.

Price schedule Part 1A, 1B and part II shall be submitted in separate sealed envelopes and shall be kept in Envelope IV.

PRICE SCHEDULE 11 Part II

For Supply of Spares and Tools

(Tender No. IPGL/ Yard Cranes /2018)

A complete list of spare parts and special tools as required for 5000 running hours of operation of the cranes with quantity, unit price and total amount to be paid by the employer shall be given in the following format. Spare Parts/Tools as listed in Schedule 10, quoted in respective schedule of price, are optional and not to be considered for evaluation of the bid. However, the bidder has to confirm that prices quoted for spares and tools will remain valid for 2 years from date of Final Acceptance

A) Spare Parts &Special Tools

Sr. No.	Description	Qty	Manufacturer's Name and Model Number	Country of Origin	CIF price (In EURO/INR)				
					Currency	Unit rate quoted		Total amount quoted	
						In Figures	In Words	In Figures	In Words
1.									
Grand Total (Price Schedule II)									

Separate sheets for 100 ton & 60 ton capacity Yard Cranes to attached.

Note: Procurement of the spares parts and special tools is optional on part of IPGL, and the prices quoted for same shall be valid for two years from the date of FAC. However same shall NOT BE TAKEN FOR EVALUATION OF THE BID.

Note: Tenderer shall submit their offer for the above entire work. Partial offer and conditional offer by any tenderer shall be liable for rejection.

Name and Signature of Tenderer

Name and Signature of Witness

SCHEDULE 12

INTEGRITY PACT

Between

"India Ports Global Limited, (IPGL) hereinafter referred to as "The Principal"

And

..... hereinafter referred to as **"The Bidder/Contractor"**

Preamble

The Principal intends to award, under laid down organizational procedures, contract/s for “Design, Manufacture, Supply, Installation, Testing, Commissioning and Guaranteeing the performance of 3 Nos All Terrain Cranes (100 Ton Capacity) and 3 NO.s Rough Terrain Cranes(60 Ton capacity Yard Cranes at Shahid Beheshti Port, Chabaha.” The Principal values full compliance with all relevant laws of the land, rules, regulations, economic use of resources and of fairness/transparency in its relations with its Bidder(s) and/or Contractor(s).

Section 1 – Commitments of the Principal

(1) The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles;

a.No employee of the Principal, personally or through family members will be in connection with the tender for, or the execution of a contract, demand, take a promise for or accept for self or third person, any material or immaterial benefit which the person is not legally entitled to.

b.The Principal will, during the tender process treat all Bidder(s) with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential/additional information through which the Bidder(s) could obtain an advantage in relation to the tender process or the contract execution.

c.The Principal will exclude from the process all known prejudiced persons.

(2). If the Principal obtains information on the conduct of any of its employees which is a criminal offence under the IPC/PC Act, or if there will be a substantive suspicious in this regard, the Principal will inform the Chief Vigilance Officer and in addition can be initiate disciplinary action.

Section 2 - Commitments of the Bidder(s)/Contractor(s)

(1) The Bidder(s)/Contractor(s) commit himself to take all measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the tender process and during the contract execution.

(a)The Bidder(s)/Contractor(s) will not directly or through any other person or firm, offer, promise or give to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material or other benefit which he/she is not legally entitled to. In order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.

(b)The Bidder(s)/Contractor(s) will not enter with other Bidders into any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submissions or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the Bidding process.

(c) The Bidder(s)/Contractor(s) will not commit any offence under the relevant IPC/PC Act; further the Bidder(s)/Contractor(s) will not use improperly, for purpose of competition, or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposals and business details including information contained or transmitted electronically.

(d)The Bidder(s)/Contractor(s) of foreign origin shall disclose the name and address of the Agent/Representatives in India, if any.

Similarly the Bidder(s)/Contractor(s) of Indian Nationality shall furnish the name and address of the foreign principals, if any. Further details as mentioned in the "Guidelines on Indian Agent of Foreign Suppliers" shall be disclosed by the Bidder(s)/Contractor(s). Further as mentioned in the Guidelines all the payments made to the Indian agent/representative have to be in Indian Rupees only. Copy of the "Guidelines on Indian Agent of Foreign Supplier" is annexed and marked as Annex-"A".

(e)The Bidder(s)/Contractor(s) will, when presenting his bid, disclose any and all payments he has made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of contract

(2)The Bidder(s)/Contractor(s) will not instigate third person to commit offences outlined above or be an accessory to such offences.

Section 3- Disqualification from tender process and exclusion from future contracts.

If the Bidder(s)/Contractor(s), before award or during execution has committed a transgression through a violation of Section 2, above or in any other form such as to put his reliability or credibility in question, the Principal is entitled to disqualify the Bidder(s)/Contractor(s) from the tender process or take appropriate action.

Section 4 – Compensation for Damages

(1)If the Principal has disqualified the Bidder(s) from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover the damages equivalent to Earnest Money Deposit/Bid Security.

(2)If the Principal has terminated the contract according to Section 3, or if the Principal is entitled to terminate the contract according to Section 3, the Principal shall be entitled to demand and recover from the Contractor penalty for delays of the Contract value or the amounts equivalents to Performance Bank Guarantee.

Section 5- Previous transgression

(1)The Bidder declares that no previous transgression occurred in the last 3 years with any other Company in any Country conforming to the anti- corruption approach or with any other Public Sector Enterprise in India that could justify his execution from the tender process.

(2)If the Bidder makes incorrect statement on this subject, he can be disqualified from the tender process or appropriate action can be taken.

Section 6-Equal treatment of all Bidders / Contractors / Subcontractors

(1)The Bidder(s)/ Contractor(s) undertake(s) to demand from all subcontractors a commitment in conformity with this Integrity Pact, and to submit it to the Principal before contract signing.

(2)The Principal will enter into agreement with identical conditions as this one with all Bidders, Contractors and Subcontractors.

(3)The Principal will disqualify from the tender process all bidders who do not sign this Pact or violate its provisions.

Section 7- Criminal charges against violating Bidder(s) / Contractor(s) / Subcontractor(s)

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Subcontractor or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor which constitutes corruption or if the Principal has substantive suspicion in this regard, the Principal will inform the same to the Chief Vigilance Officer.

Section 8- Pact Durations

This Pact begins when both parties have legally signed it. It expires for the Contractor 12 months after the last payment under the contract, and for all other Bidders 6 months after the contract has been awarded.

If any claim is made / lodged during this time, the same shall be binding and continue to be valid despite the lapse of this Pact as specified above, unless it is discharged / determined by Managing Director, IPGL

Section 9 - Other provisions

(1) This agreement is subject to Indian Law, Place or Performance and Jurisdiction is the Registered Office of the Principal, i.e., Mumbai.

(2) Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.

(3) If the Contractor is a partnership or a consortium, this agreement must be signed by all partners or consortium members.

(4) Should one or several provisions of this agreement turn out to be invalid, the remainder of this agreement remains valid. In this case the parties will strive to come to an agreement to their original intentions.

(For and on behalf of Principal) (Office seal)

Place.....

Date.....

Witness 1.....

(Name & Address).....

Witness 2.....

Place.....

Date.....

Witness 1:

(Name & Address)

Witness 2:

Schedule 13
CHECK LIST

INDIA PORTS GLOBAL PRIVATE LIMITED

Tender: No. IPGL/Yard Cranes/ 2018

CHECK LIST OF DOCUMENTS TO BE SUBMITTED ALONG WITH TECHNICAL BID.

All the pages of the document submitted under this tender shall be properly and neatly numbered inserial, and same shall be reflected in the summary to be submitted as check list to the offer in the following manner for easy identification of the documents during evaluation.

Sl. No.	DETAILS OF DOCUMENTS TO BE SUBMITTED
1.	A covering letter along with check list giving details of the documents being submitted with tender confirming validity of bid for 180 days and submission of Earnest Money Deposit- Envelope-1 so super scribed with the contents therein.
2.	Earnest Money Deposit as per tender condition- Envelope-2 so super scribed with the contents therein.
3.	The tender document is to be submitted in two sets, one being marked as " ORIGINAL " and other as " COPY ". The original and copy of the Tender shall be submitted (Technical Bid), with each page of it duly signed by the authorised person and stamped with company's seal in token of having been read and accepted the tender conditions along with Letter of application cum Tender form duly signed by the person / persons who is/are competent to sign (Annex III of Vol.I of this tender document) and TECHNICAL BID. - Envelope 3 so super scribed with the contents therein.
4.	Price Bid As per Schedule 11 (Volume-I) - Envelope-4 so super scribed with the contents therein Part 1A ,1B and part II shall be submitted in separate sealed envelopes and all these three envelopes shall be kept in Envelope IV
5.	Schedule 11 Schedule of Prices is in Part 1, 2, & 3. All the 3 Parts duly filled in shall be kept in Envelope 4.
6.	Particulars of the Tenderers as specified in the Schedule 1 (Volume-I) of this tender document.
7.	Financial Details duly supported by audited reports by certified chartered accountant for last three years in Schedule-2
8.	Technical data of the crane as per (Volume-II) of 100 ton (AT) and 60 Ton (RT) Yard Cranes of this tender document.
9.	Work Schedule as per Schedule 3 (Volume-I) of this tender document:
10.	Details of the training programme of various categories of employer's employees as per Schedule 4 & 4 A (Volume-I) of this tender document.
11.	Quality Assurance Plan indicating all activities steps by step at various stage of project as per Schedule 5 (Volume-I) and details of instruments for Testing & quality control as per Schedule 6 (Volume-I) of this tender document
12.	Details of bought out items and its quality certification plan
13.	Details of Sub Contractor involved in the various activities according to Schedule 7 (Volume-I) of this tender document
14.	Detailed drawings of various arrangements of the crane as per this tender document.

15.	Arrangement for importing spare parts, tie up with local firms for supply of spare parts, if any and arrangement for after sales service. Tenderer shall submit the information as per Schedule 8 (Volume-I) of the Tender Document.
16.	Statements of deviations as per Schedule 9 (Volume-I) of tender document.
17.	List of spare parts as per (Volume-II) applicable for 100 Ton (AT) and 60 Ton (RT) capacity Yard Cranes, Schedule-10 and Operation & Maintenance manual as per Schedule 10-A.
18.	Information regarding any current litigation.
19.	Details of Warranty Support programme as per Contract Conditions.
20.	MOU/Agreement entered in technical collaboration (if applicable)
21.	Undertaking to ensure integrity as per Schedule 12 of Volume I.
22.	Any other details, which shall establish the technical competency and any deviation from technical specification
23.	Non Disclosure Agreements Schedule – 14
24.	Details of Key Person as per Schedule 15
25.	Current commitment in hand as per Schedule 16
26.	Details of work completed in past as per Schedule 17
27.	Experience in similar works as per Schedule 18

Schedule – 14
Non Disclosure Agreement

THIS AGREEMENT is made this _____ day of _____, 2018

Between

Board of Directors of Indian Global Ports Private Limited, incorporated under the Companies Act(hereinafter called the 'Board' which expression shall, unless excluded by, or repugnant to the context, be deemed to include the Board of Directors of Indian Global Ports Private Limited, its successors and assigns) of the ONE PART

AND.

M/s , a Company incorporated in (Country)
Under the and having its office at.....

.....
.....
.....

..... (hereinafter" referred to as "Contractor" which expression shall include its successors and assigns) of the other part;

WHEREAS:

(1) By Tender No..... (The "Tender"), offers were invited from Contractors for the work of..... for Indian Global Ports Private Limited (the "Project");

(2) M/s made an offer to act as the Contractor as per the terms and conditions of the tender; and

(3) After evaluation of the proposals/ offers received, the Board has engaged M/s as the Agency for carrying out..... (Work Title), subject to signing of the Confidentiality

Agreement between the Board and the Contractor and conveyed to the Contractor by its(Work Order signatory) vide Work Order No dtd. __/__/201_ which was duly accepted by the Contractor vide its letter dated __/__/201_.

NOW, THEREFORE, in consideration of the mutual agreements contained herein, the Contractor covenants with the Board as follows:

1. All business, financial, operational and other information and data, of whatever kind and in whatever form, relating to the Board, which is disclosed or made known or comes to the knowledge of the Contractor (including but not limited to its representatives, professional advisors, employees and Authorised Distributor / Dealer / Licensee,) by the Board or on the Board's behalf (including but not limited to its representatives, advisors, employees and Authorised Distributor / Dealer / Licensee,) (collectively referred to as "Confidential Information") will be held incomplete confidence and will not be used for any purpose other than directly in connection with the scope of services described in the tender.

2. The Contractor will not, without the prior written consent of the Board or its authorised person/s, disclose or otherwise make available whole or any part of the Confidential Information to any third party except in accordance with the terms of this Agreement.

3.The Contractor will be entitled to copy and circulate the Confidential Information to its only such directors, officers and employees and to such of its professional advisors who are directly concerned with fulfilment of the scope of services as per the terms and conditions of the tender and to whom knowledge of such information is necessary for such purpose. All persons to whom any Confidential Information is disclosed shall treat the same as confidential and use the same solely for due discharge of its obligations under the Scope of Services stated in

the tender. The Contractor will be responsible for procuring their compliance with the terms of this Agreement as if they were subject to the same obligations to the Company as the Contractor is subject to hereunder.

4. The restrictions, obligations and liabilities contained in this Agreement shall not apply to any information which:

- a) Was already in the public domain at the time of its disclosure to the Contractor by the Board; or subsequently becomes part of the public domain through no breach by the Contractor of its obligation under the Agreement.
- b) is generally available to or accessible by, the public or, after such disclosure, becomes generally available to, or accessible by the public, other than by reason of a breach of any undertaking by the Contractor contained in this Agreement; or
- c) is required to be disclosed by the Contractor by applicable law or regulation or judicial authority, provided that the Contractor agrees, to notify, the Board in writing, duly signed by an authorised signatory, as soon as possible, upon becoming aware of any such requirement and confirming the necessity of the disclosure prior to such disclosure; The Contractor shall promptly notify the Board in writing if any confidential information is required to be disclosed by law or other regulation and will co-operate with the Board regarding the timing and content of such disclosure or any action which the Board may elect to take to challenge the validity of such requirement unless such cooperation exposes the Contractor to claims, losses, damages or other liability for which the Contractor does not receive indemnification from the Board, and the Contractor undertake that any such disclosure shall be the minimum required by the relevant law or regulation in order for the Contractor to comply with its obligations there under.

5. The Contractor will not make, or permit its officers, directors, employees and professional advisors to make or procure or solicit or assist any other persons to make, any announcement or disclosure of the Confidential Information without the Board's prior written consent.

6. The Contractor and the Board shall individually keep a record of the Confidential Information provided by the Board to it in writing ("Confidential Information"). The Contractor shall, forthwith upon receipt of a written request from the Company or completion of the assignment as per the tender or if the Contractor ceases to act as the Agency for.....(Work Title) of the Board:

- (a) Return to the Board any Confidential Information in the Contractor's possession or control of, or in the possession or control of, any of its employees, Authorised Distributor / Dealer / Licensee, or professional advisors, together with all copies thereof, and
- (b) Expunge all Confidential Information from any computer, word processor or similar device into which it has been programmed by the Contractor or its professional advisors on its behalf.
- (c) Not make use of the information, contained in the confidential information for any of its business operations.

The Contractor acknowledges that neither the return of any Confidential Information nor the expunging of any Confidential Information from its records shall release it from its obligations under this Agreement.

7. The obligations contained in this Agreement are continuing and, in particular, shall survive the completion of the project.

8. The Contractor agrees and acknowledges that the Board may be irreparably harmed by the breach of the terms hereof and damages may not be an adequate remedy and that injunctive relief is an appropriate remedy to protect the rights of a party with respect to its Confidential Information. The Contractor shall be responsible for the breach of any of its covenants and obligations in this Agreement and will indemnify the Board from and against any claims, costs, expenses, losses or damages (including reasonable attorneys' fees) that are actually incurred by the Board and that are directly and solely attributable to the breach by the Contractor of its covenants and obligations in this Agreement. The Contractor further confirms that it is acting in this matter as principal and not as agent for any other person.

9. The rights, powers and remedies provided in this Agreement shall be in addition to, and not in substitution for, any other rights, powers and remedies provided by law. No failure or delay in exercising any right, power or privilege hereunder will operate as a waiver thereof nor will any single or partial exercise of any right, power or privilege preclude any further exercise thereof or the exercise of any other right, power or privilege hereunder. The terms of this Agreement and the Contractor's obligations hereunder may only be amended or modified by written agreement between the Contractor and the Board.'

10. This Agreement shall be governed by and construed in accordance with Indian law. The parties hereby agree to submit to the jurisdiction of the courts of Mumbai.

11. If at any time any term or provision in this Agreement shall be held to be illegal, invalid or unenforceable, in whole or in part, under any rule of law or enactment, such term or provision or part shall to that extent be deemed not to form part of this Agreement, but the enforceability of the remainder of this Agreement shall not be affected.

12. This Agreement shall be freely assigned by the Board, with prior written notice to the Contractor, to any person or persons who are substituted in all in the interests or rights or obligations of the Board for the development of the Project.

13. All questions, disputes and differences arising under or in relation to this Agreement shall be referred to (Work Order signatory) of The Board for consideration. The decision of (Work Order signatory) shall be final, conclusive and binding on all the parties to the Agreement.

IN WITNESS WHEREOF, the parties have caused this Non-Disclosure Agreement to be executed by their respective duly authorised officers as of the day and year first hereinabove written.

Authorized Signatory

Managing Director on Behalf of the Board of Directors of

For M/s.

Indian Ports Global Private Limited

In Present Of

In Present Of

.....
...
.....
...
.....
...

.....
.....
.....

SCHEDULE 15

DETAILS OF KEY PERSONNEL

Details of key personnel involved in administration and execution of the subject work till completion, are to be furnished. The information in this regard should be submitted in below mentioned format and separate sheets may be used to furnish necessary details, if required.

No.	Name in full	Designation	Qualification	Experience
1.				
2.				
3.				
4.				
5.				
6.				
7.				
8.				
9.				
10.				

Signature & Seal of the Tenderer

SCHEDULE 16
CURRENT COMMITMENTS IN HAND

Tenderer should provide necessary information about their current commitments on all Contracts that have been awarded, or for which a 'Letter of Intent' is placed or 'Letter of Acceptance' has been received or for Contracts approaching towards completion and full completion certificate has yet to be issued. The information in this regard should be submitted in below mentioned format and separate sheets can be used to furnish necessary details.

In support of submitted information, it is very essential to submit copies of orders in hand or copies of 'Letter of Intent' / work orders as the case may be.

	Name of the Client	Order number / Reference number & Date	Order value	Date of Completion as per the Order	Estimated date of Completion
1.					
2.					
3.					
4.					

Signature & Seal of the Tenderer

SCHEDULE 17

DETAILS OF WORKS COMPLETED IN PAST

Tenderer should provide necessary information about Works completed during last 03 years for which completion certificate or performance certificate is already issued by the Client. The information in this regard should be submitted in below mentioned format and separate sheets can be used to furnish necessary details.

In support of submitted information, it is very essential to submit copies of orders executed in past along with satisfactory performance certificates issued by Clients.

No	Name of the Client	Order number or Reference number & Date	Order value	Date of Completion as per the Order	Actual date of Completion
1.					
2.					
3.					
4.					

Signature & Seal of the Tenderer

SCHEDULE 18

EXPERIENCE IN SIMILAR WORKS

Reference: -1

The information about experience in similar Works should be submitted in below mentioned format and separate sheets must be used for each reference.

You are advised to furnish details about similar works as stipulated in the Tender. In support of submitted information, it is very essential to submit copies of order/s executed along with satisfactory performance certificate issued by Client/s.

1.	Client's Name:	
2.	Contract / Order number and Date	
3.	Name of the Contract:	
4.	Client's Address in full:	
5.	Name of Client's Contact person:	
6.	Client's Telephone Number/s	
7.	Client's fax number	
8.	Contract / Order value	
9.	Completion period as per Contract / Order	
10.	Date of Actual completion Of Contract / Order	
11.	Brief details of Contract/Order	

Signature & Seal of the Tenderer

SCHEDULE 18
EXPERIENCE IN SIMILAR WORKS

Reference: -2 (if any)

1.	Client's Name:	
2.	Contract / Order number and Date	
	Name of the Contract:	
4.	Client's Address in full:	
5.	Name of Client's Contact person:	
6.	Client's Telephone Number/s	
7.	Client's fax number	
8.	Contract / Order value	
9.	Completion period as per Contract / Order	
10.	Date of Actual completion of Contract / Order	

11.	Brief details of Contract/Order
------------	--

Signature & Seal of the Tenderer

VOLUME – II

TECHNICAL SPECIFICATIONS

YARD CRANES

February 2018

YARD CRANE

ALL TERRAIN DIESEL DRIVEN HYDRAULIC, TYRE MOUNTED TELESCOPIC CRANE OF 100 TONS CAPACITY

- 1.0 This specification covers the design, manufacturing, inspection, testing and commissioning at site of 100 Tons all terrain cranes as specified below.

IPGL intends to procure 3 (three) Nos. of all terrain, diesel driven, hydraulic, tyre mounted, telescopic crane of 100 tons capacity under the hook for handling break bulk cargo in the stack yard at Chabahar Port Multipurpose terminal.

The design and manufacture of this unit should comply with the well-known standards such as: ISO, FEM, IEEE, ASME, IEC, JIS, EN, ECC, AWS, SIS, and DIN.

2.0 Environmental conditions

- Temperature range: 0 to +50°C
- Humidity: relative humidity up to 99%
- Height from sea level: 0
- Environment: Dusty, corroding and salty environment
- Permissible wind speed when the units are working: 72 km/h

3.0 Main Conditions

- The crane should be of All Terrain and telescopic boom type.
- Suggested crane should be designed for Chabahar port conditions.
- The crane must work in the port conditions for continuous 20 hours per day and 7 days of the week.
- Hoisting, Luffing and slewing speeds should be suitable for the intended operation, i.e handling/ loading/ unloading of break bulk cargo in stack yard.
- The capacity of crane should be 100 tons under the hook.
- The length of boom in fully open mode should be at least 60 m (Without JIB). The lifting capacity will be calculated in accordance with relevant DIN /ISO / any other equivalent standards and to be certified.
- The crane should be able to rotate (slewing) 360° without any change in their capacity during operation/rotation.
- The lifetime of the parts must be at least 25,000 running hours.

4.0 Auxiliary Systems

The crane must be equipped with the following systems:

- Separate centralized lubrication system for main parts that need lubrication.
- Appropriate warning lights (rotary or flashing strobes), motion alarms (horn, acoustic alarms), luminous, emergency shutdowns and other necessary warning lights and alarms must be installed.
- Adequate floodlights for illuminating the working area, operator's cab.

- Lightning protection system.
- The lighting system should be of anti-vibration mount type to prevent failure due to vibrations and in accordance with existing standards of Destination Port.
- All stairs, bolts and nuts should be resistant against corrosion caused by humidity and stairs should be safe enough.
- One spare tyre with ring for the crane should be supplied as spare.
- Fire extinguishers should be installed in all necessary locations.
- All of special and standard tools for maintenance must be supplied.
- Air compressor for adjusting the tyre air pressure and its necessary equipment.
- Fuel tank should be equipped with drain valve and fuel indicator separately.
- Fuelling must be done easily and the fuel tank must be installed in the lowest position.
- All joysticks must be equipped with dead man protection system.

5.0 **Operator's Cabin (and Driver's Cabin):**

The operator's cabin should have also the capability of running the unit operations from there. Each cabin must be equipped with the followings:

- Air conditioning in the cabin to keep the temperature around 22°C with relative humidity between the standard limits.
- Maximum acceptable noise level in cabs: 75 dBA.
- Cab windows should have wipers for cleaning and also FW spray especially the upper window, to provide the best possible view.
- Also all the cab windows should be able to be cleaned manually.
- Cab windows should be made of tinted safety glass.

6.0 **Engine**

- The crane can have one or two separate engines for its movement and operation, i.e. for the crane and the carrier, and in case of using one engine for both operations, its maximum power should be considered in such a way that it does not cause rapid wearing out of the engine.
 - Since the unit must be designed in a way that its operations can be controlled from operator's cabin, if the crane unit uses two separate engines, both of them must also be controllable from the operator's cabin.
 - The crane engines must be supplied and installed from reputable and well-known brands (from original manufacturer's country) with easy maintenance requirements and in compliance with the relevant port's operational conditions.
- * Japanese companies can use the engines with reputable Japanese brands.
- All companies must introduce an agent for the above said engines for maintenance works and supply of spare parts.

7.0 **Hydraulic System**

- The crane hydraulic system must be designed based on the regional weather conditions and

easy accessibility and maintenance capability that can avoid temperature increase more than permissible level.

- All couplings and seals used in the unit must be capable enough to tolerate temperature increase and avoid oil leakage of the system.

8.0 **Boom**

- Hydraulically telescoping type with one base section and other telescopic sections, capable of telescoping not less than 60 Mts. The crane boom should be designed in a way that it can tolerate possible tensions as well as fractures.

9.0 **Signals & Displays**

- All important signals and displays of the crane including engine functions (oil pressure, engine RPM, water temperature etc.) and relevant displays of hydraulic system (including hydraulic oil temperature) and other necessary indicators must be installed in the unit.

10.0 **Crane Control System**

- The crane monitoring system must be capable of showing operational conditions of the unit including boom angle, boom length, load under hook and also capability of showing the lifting position(s) of the crane.
- The crane monitoring system must also be capable of displaying the crane problems/defects and their relevant locations to ease the maintenance works when using the drawings.
- Monitoring system should be in English.
- The electronic components should have protections for withstanding the environmental conditions described above.(Such as temperature, humidity, dust)

11.0 **Design Rules**

Manufacturer should cover below items with FEM or equivalent standard for its design:

- Classification and loading on structures and movement mechanisms.
- Stress calculation for structures.
- Fatigue calculations and selection of mechanisms' component.
- Stability and safety factor against movements by the wind.
- The seller should foresee all necessary conditions in its design and should give the most compatible design for environment of the said port.
- The seller should carry out the final test after commissioning.

12.0 **Materials and Structural Steels**

- All parts of load bearing structure should be weld able low carbon steel and free from defect and also have well-known certificate from appropriate certification body.

13.0 **Warning / Caution Instructions**

- In all necessary positions and locations of the crane that caution instructions are needed, a note plate should be installed to warn the personnel in Farsi and English languages.

14.0 **List of Equipment Manufacturers**

- All equipment must be supplied from original manufacturer's country (from Western Europe) and also not from their stock.
- Only Japanese companies can use equipment made by reputable Japanese companies

15.0 **Hook Block** - Multi-sheave Hook Block with rope guard and rotating hook with sling catcher. Means shall be provided to secure the Hook with chassis to prevent swinging while travelling. To provide

(i) double hook, 3 sheaves hook block approx...50t – 1 no. (ii) Single hook, 1 sheave, hook block approx...22t – 1 no. (iii) Crane hook, 7.5 t approx... – 1 no.

The crane shall be able to climb up the gradient as per manufacturer's standard design.

16.0 **CARRIER**

Travelling speed: Minimum 75 KMPH

Turning radius: to be as per manufacturer's standard design and as short as possible for this type of crane.

No. of axles: as per manufacturer's standard design. ALL AXLES STEERED.

Engine: 4 cycles, 8 cylinders, water cooled, direct Injection turbo-charged diesel engine with intercooling. International reputed manufacturers.

Suitable torque converter with power shift transmission, multiple forward and reverse speeds, as per manufacturer's standard design

Suspension: as per manufacturer's standard design

Brake system: Service brake, Parking brake and Auxiliary brake.

Steering: Hydraulic power steering, preferably with 3/4 steering modes as per manufacturer's standard design

Outriggers: Hydraulic out and down type outriggers which can be operated from cab. Outriggers should have locking arrangements. (as per manufacturers' standard design)

Tyres: Of reputed brands. Size as per manufacturer's standard design

Electric system: 24V/ 12V as per manufacturer's standard design

Fuel Tank capacity: approx.. 500L

Towing hook (front and rear, eye type)

17.0 **Safety Devices:**

Emergency steering device, Engine over speed alarm, Three-point seat belt (Driver), Suspension lock, Electric adjustable side mirrors, Warning reflector, Engine management & warning system, Transmission management & warning system, Radiator coolant level warning device, Low air warning device, Brake light / parking light disconnection warning device, Rear view camera, Brake wear indicator

18.0 Supply of initial spares like filters, belts etc. for scheduled servicing, as per manufacturer recommendations for successful operation for a period of 2 years (or) 4000 hours of operation whichever is earlier.

19.0 Supply of guaranteed spares, required for one year or 1500 hours of operation, after Completion of warranty whichever is earlier.

20.0 Supply of standard tools and gauges that are normally supplied along with each Equipment at free of cost.

21.0 Supply of operation and maintenance manuals, spare parts catalogues and other Documents as detailed in the Technical specifications including soft copy.

22.0 Any item not included in the specifications but necessary for efficient & effective operation of the crane shall be indicated in the bid and supplied with the crane.

PREFERRED / INDICATIVE MANUFACTURERS FOR MAJOR COMPONENTS FOR THE EQUIPMENTS

PREFERRED MANUFACTURERS

MOBAIL CRANE LOM

Description	Manufacturer /Supplier	Country
Diesel Engine	VOLVO CUMMINS BENZ	Sweden/UK UK Germany
Brakes	WEBASTOR KNORR	Germany Germany
Differential	KESSLER	Germany
Gearbox	ZF	Germany
Main Slewing Bearing	ROTHERDE	Germany
Drivers Cabin	Depend Manufacturer	
All Hydraulic Pumps	BOCH REXROTH	Germany Germany
All Hydraulic Cylinders	MONTANHYDRAULIC BOSCH REXROTH	Germany Germany Germany
All Wire Ropes	CASAR PFEIFFER	Germany Germany
Operator Cabin	Depend Manufacturer	
Air Conditioning	WOLFER LG MITSUBISHI	Germany Korea Japan
	BOSCH	Germany
Compressors	MERSEDES ATLAS COPCO	Germany Germany
Paint	FELDA SUDING INTERNATIONAL HEMPLE	Germany Germany Germany Denmark
Tires	MICHELIN BRIDGESTON	Germany Japan
BOOM	Depend Manufacturer	
Axles	KESSLER	Germany
Truck Chassis	Depend Manufacturer	
All Sheavings	Depend Manufacturer	
All Winches	Depend Manufacturer	
Hook	HANN MOHR	Netherlands Germany
Hydraulic Directional AND Proportional Control Valves	BOUSH REXROTH	Germany Germany
Joysticks & Push Buttons	FFG GESSMAN	Germany Germany
Load Sensors	Philips	Netherlands

The other brands may be indicated by the tenderers. However, the acceptance of the same will be subject to confirmation by the tender holder prior to end of technical evaluations.

YARD CRANE

ROUGH TERRAIN DIESEL DRIVEN HYDRAULIC, TYRE MOUNTED TELESCOPIC CRANE OF 60 TONS CAPACITY

1.0 This specification covers the design, manufacturing, inspection, testing and commissioning at site of 60 Tons rough terrain crane as specified below.

IPGL intends to procure 3 (three) Nos. of rough terrain, diesel driven, hydraulic, tyre mounted, telescopic crane of 60 Tons capacity for handling break bulk cargo in the stack yard at Chabahar Port Multipurpose terminal.

The design and manufacture of this unit should comply with the well-known standards such as: ISO, FEM, IEEE, ASME, IEC, JIS, EN, ECC, AWS, SIS, and DIN.

2.0 Environmental conditions

- Temperature range: 0 to +50°C
- Humidity: relative humidity up to 99%
- Height from sea level: 0
- Environment: Dusty, corroding and salty environment
- Permissible wind speed when the units are working: 72 km/h

3.0 Main Conditions

- The crane should be of Rough Terrain and telescopic boom type. Suggested crane should be designed for Destination Port conditions.
- The crane must work in the port conditions for continuous 20 hours per day and 7 days of the week.
- Hoisting, Luffing and slewing speeds should be suitable for the intended operation, i.e handling/ loading/ unloading of break bulk cargo in stack yard.
- The capacity of crane should be 60 Tons under the hook on outriggers, boom fully retracted. The crane should be able to rotate (slew) 360 degrees with this load.
- The length of boom in fully open mode should be at least 29 m. (Without JIB)
- The crane should be able to rotate (slewing) 360° without any change in their capacity during operation/rotation.
- The lifetime of the parts must be at least 25000 running hours.

4.0 Auxiliary Systems

The crane must be equipped with the following systems and cost shall be included in the quoted CIF value of the crane.:

- Separate centralized lubrication system for main parts that need lubrication.
- Appropriate warning lights (rotary or flashing strobes), motion alarms (horn, acoustic alarms), Luminous, emergency shutdowns and other necessary warning lights and alarms must be installed.
- Adequate floodlights for illuminating the working area, operator's cab.
- Lightning protection system.
- The lighting system should be of anti-vibration mount type to prevent failure due to vibrations and in accordance with existing standards of Chabahar Port.
- All stairs, bolts and nuts should be resistant against corrosion caused by humidity and stairs should be safe enough.

- One spare tyre with ring for the crane should be supplied.
- The manufacturer is bound to suggest common sizes of tires for its crane.
- Fire extinguishers should be installed in all necessary locations.
- All of special & standard tools for maintenance must be supplied. Each crane shall be equipped with its standard tool-box.
- Air compressor for adjusting the tires air pressure and its necessary equipment.
- Fuel tank should be equipped with drain valve and fuel indicator separately.
- Fuelling must be done easily and the fuel tank must be installed in the lowest position.
- All joysticks must be equipped with dead man protection system.

5.0 Operator's Cabin:

The operator's cabin should have also the capability of running the unit operations from there. Each cabin must be equipped with the followings:

- Air conditioning in the cabin to keep the temperature around 22°C with relative humidity between the standard limits.
- Maximum acceptable noise level in cabs: 75 dBA.
- Cab windows should have wipers for cleaning and also FW spray especially the upper window, to provide the best possible view.
- Also all the cab windows should be able to be cleaned manually.
- Cab windows should be made of tinted safety glass.

6.0 Engine

The crane engine/s must be supplied and installed from reputable and well-known brands (from original manufacturer's country) with easy maintenance requirements and in compliance with the relevant port's operational conditions.

7.0 Hydraulic System

The crane hydraulic system must be designed based on the regional weather conditions and easy accessibility and maintenance capability that can avoid temperature increase more than permissible level.

All couplings and seals used in the unit must be capable enough to tolerate temperature increase and avoid oil leakage of the system.

8.0 Boom

Hydraulically telescoping type with one base section and other telescopic sections, capable of telescoping not less than 29 Mts. The crane boom should be designed in a way that it can tolerate possible tensions as well as fractures.

9.0 Signals & Displays

All important signals and displays of the crane including engine functions (oil pressure, engine RPM, water temperature etc.) and relevant displays of hydraulic system (including hydraulic oil temperature) and other necessary indicators must be installed in the unit.

10.0 Crane Control System

- The crane monitoring system must be capable of showing operational conditions of the unit including boom angle, boom length, load under hook and also capability of showing the lifting position(s) of the crane.
- The crane monitoring system must also be capable of displaying the crane problems/defects and their relevant locations to ease the maintenance works when using the drawings.
- Monitoring system should be in English.
- Electronic Safe Load Indicator (SLI). It shall continuous display all essential data, information and instructions enabling the crane to be operated within the designed parameters. It shall all the time provide information viz. boom length, boom angle, boom tip height, radius, rated load, load being lifted, etc. On reaching overload/unsafe condition, it shall cut-off the unsafe operations, as well as gives warnings through audible-visual alarm.
- The electronic components should have protections for withstanding the environmental conditions described above. (Such as temperature, humidity, dust)

11.0 Design Rules

Manufacturer should cover below items with FEM or equivalent standard for its design:

- Classification and loading on structures and movement mechanisms.
- Stress calculation for structures.
- Fatigue calculations and selection of mechanisms' component.
- Stability and safety factor against movements by the wind.
- The seller should foresee all necessary conditions in its design and should give the most compatible design for environment of the said port.
- The seller should carry out the final test after commissioning.

Test Certificate for Hook and Boom to be furnished along with the Machine

12.0 Materials and Structural Steels

All parts of load bearing structure should be weldable low carbon steel, and free from defect and also have well-known certificate from appropriate certification body.

13.0 List of Equipment Manufacturers

All equipment must be supplied from original manufacturer's country (list attached)

14.0 **Hook Block** - Multi-sheave Hook Block with rope guard and rotating hook with sling catcher. Means shall be provided to secure the Hook with chassis to prevent swinging while travelling.

15.0 Warning / Caution Instructions

In all necessary positions and locations of the crane that caution instructions is needed, a note plate should be installed to warn the personnel in Farsi and English languages.

16.0 CAPACITY (85% OF THE TIPPING LOAD)

ON OUTRIGGERS FULLY EXTENDED WITH 360 DEGREE SLEW:-

The Crane must be capable of lifting not less than 60T at a clearance of not less than 3 Meters from the central axis of rotation with fully retracted boom & fully extracted outriggers and must be capable of slewing in 360 degree (The lifting capacities indicated are for the load rating of 85% of the tipping load)"

- 17.0 **TRANSMISSION:** Suitable torque converter with power shift transmission multiple forward and reverse speeds.
- 18.0 **STEERING:** Hydraulic power steering with three/four steering modes.
- 19.0 **DRIVE:** Four wheel drive
- 20.0 **OUTRIGGERS:** Hydraulic out and down type outriggers/scissor type out riggers which can be operated from cab. Outriggers should have locking arrangements.
- 21.0 **HOISTING:** The hoisting operation should be fail safe with limit switch to prevent over hoisting and provided with either fully hydraulic/fully Pneumatic/Air over Hydraulic Brakes
- 22.0 **SWING:** Hydraulic swing for 360 deg. Continuous rotation, free slew mode for precise placement of load fitted with spring applied hydraulically released brake system. Audio signal while slewing and slew lock shall be provided.
- 23.0 **BRAKES:** Fully hydraulic/air over hydraulic/Fully Pneumatic brakes on all wheels. Brakes shall capable of holding the machine in 1:10 slopes. Parking brake shall also be capable of holding the machine in 1:10 slopes.
- 24.0 **HYDRAULIC PUMP:** Suitable hydraulic pump of adequate capacity.
- 25.0 **TRAVEL SPEED:** Maximum speed Not less than 30 KMPH.
- 26.0 **ELECTRICAL SYSTEM:** 24V electrical system with sufficient lights in front & rear. Suitable starter Motor with sufficient K.W.
- 27.0 **SAFETY SYSTEM:** Safe load moment indicator with audio-visual warning system. The system should provide electronic display of radius, boom length, tip height, boom angle relative load movement & maximum permissible load.
- 28.0 **INSTRUMENT PANEL:** Panel shall consist of lub.oil temperature gauge, Lub oil pressure gauge, high water temperature gauge, hyd. system pressure gauge, parking brake indicator, limit switch/indicator for over hoisting/lowering, rear steer indicator, outrigger locking indicator & Slew lock indicator.
- 29.0 **LITERATURES:** The bidder shall supply following literature free of cost.
- I) O&M manual : 02Nos. Per machine
 - II) Parts manual : 02Nos. Per machine
 - III) Service manual : 02Nos. Per machine
 - IV) PMC in book Form (Covering daily servicing to major servicing) : 05Nos. Per machine

- 30.0 **LUBRICANTS:** The bidder shall furnish the lub.oil particulars for all the compartments viz. engine, diesel, hyd. system, transmission brake fluid (ie. Grade, make, capacity, periodicity of changing etc.,) if oil are of imported brand equivalent Indian brands to be furnished.
- 31.0 **Test Certificate:** Test certificate for the crane as well as Hook and Boom to be furnished from statutory authority
- 32.0 **SPARES:**
- A Supply of initial spares like filters, belts etc. for scheduled servicing, as per manufacturer recommendations for successful operation for a period of 2 years (or) 4000 hours of operation whichever is earlier.
 - B Supply of guaranteed spares, required for one year or 1500 hours of operation, after completion of warranty whichever is earlier.
 - C Supply of standard tools and gauges that are normally supplied along with each Equipment at free of cost.
 - D Supply of operation and maintenance manuals, spare parts catalogues and other Documents as detailed in the Technical specifications including soft copy.
 - E Any item not included in the specifications but necessary for efficient & effective operation of the crane shall be indicated in the bid and supplied with the crane.

PREFERRED / INDICATIVE MANUFACTURERS FOR MAJOR COMPONENTS FOR THE EQUIPMENTS

PREFERRED MANUFACTURERS

MOBAIL CRANE LOM

Description	Manufacturer /Supplier	Country
Diesel Engine	VOLVO CUMMINS BENZ	Sweden/UK UK Germany
Brakes	WEBASTOR KNORR	Germany Germany
Differential	KESSLER	Germany
Gearbox	ZF	Germany
Main Slewing Bearing	ROTHE ERDE	Germany
Drivers Cabin	Depend Manufacturer	
All Hydraulic Pumps	BOCH REXROTH	Germany Germany
All Hydraulic Cylinders	MONTANHYDRAULIC BOSCH REXROTH	Germany Germany Germany
All Wire Ropes	CASAR PFEIFFER	Germany Germany
Operator Cabin	Depend Manufacturer	
Air Conditioning	WOLFER LG MITSUBISHI	Germany Korea Japan
	BOSCH	Germany
Compressors	MERSEDES ATLAS COPCO	Germany Germany
Paint	FELDA SUDING INTERNATIONAL HEMPLE	Germany Germany Germany Denmark
Tires	MICHELIN BRIDGESTON	Germany Japan
BOOM	Depend Manufacturer	
Axles	KESSLER	Germany
Truck Chassis	Depend Manufacturer	
All Sheavings	Depend Manufacturer	
All Winches	Depend Manufacturer	
Hook	HANN MOHR	Netherlands Germany
Hydraulic Directional AND Proportional Control Valves	BOUSH REXROTH	Germany Germany
Joysticks & Push Buttons	FFG GESSMAN	Germany Germany
Load Sensors	Philips	Netherlands

The other brands may be indicated by the tenderers. However, the acceptance of the same will be subject to confirmation by the tender holder prior to end of technical evaluations.